


AD-A143 496


NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS 1/2
SPAUDING POND BROOK (U) CORPS OF ENGINEERS WALTHAM MA
NEW ENGLAND DIV JUN 81

UNCLASSIFIED

F/G 13/13

NL





MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

**SHETUCKET RIVER BASIN
NORWICH, CONNECTICUT**


AD-A143 496

**SPAULDING POND BROOK
SITE NO. 2**

**DIKE CT 01712
DAM CT 00203**

**PHASE 1 INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM**

DTIC FILE COPY



DTIC
ELECTE
S JUL 25 1984 **D**

**DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS.**

JUNE 1981

DISTRIBUTION
Approved by
Date

84 07 24 103

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER CT 00203, CT 01712	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Spaulding Pond Brook, Site No. 2 NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE June 1981
		13. NUMBER OF PAGES 70
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		18a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Shetucket River Basin Norwich, Conn. Spaulding Pond Brook		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) Dam No. 2 along Spaulding Pond Brook is an earth embankment structure. It is 12 ft. wide at the crest, 200 ft. long and 16 ft. high. Both the upstream and downstream slopes are about 3H:1V. As a result of the visual inspection, hydrologic and hydraulic computations and the review of the design plans and specifications, the dam is considered to be in GOOD condition. The dam is classified as SMALL in size and has a HIGH hazard potential structure in accordance with the Corps of Engineers.		



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02254

REPLY TO
ATTENTION OF:

NEDED

AUG 1 1981

Honorable William A. O'Neill
Governor of the State of Connecticut
State Capitol
Hartford, Connecticut 06115

Dear Governor O'Neill:

Inclosed is a copy of the Spaulding Pond Brook Site No. 2 Dam & Dike (CT-00203 and CT-01712) Phase I Inspection Report, prepared under the National Program for Inspection of Non-Federal Dams. This report is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. I approve the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is vitally important.

Copies of this report have been forwarded to the Department of Environmental Protection, and to the owner, the City of Norwich, CT. Copies will be available to the public in thirty days.


I wish to thank you and the Department of Environmental Protection for your cooperation in this program.

Sincerely,

WILLIAM E. HODGSON, JR.
Colonel, Corps of Engineers
Acting Commander and Acting Division Engineer

Incl
as stated

Accession For	
NTIS GRA&I	<input checked="checked" type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	
By	
Distribution/	
Availability Codes	
Dist	Avail and/or Special
A/1	



SHETUCKET RIVER BASIN NORWICH, CONNECTICUT

SPAULDING POND BROOK

SITE NO. 2

DIKE CT 01712

DAM CT 00203

PHASE 1 INSPECTION REPORT NATIONAL DAM INSPECTION PROGRAM



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS.

JUNE 1981

NATIONAL DAM INSPECTION PROGRAM

PHASE I INSPECTION REPORT

	<u>DAM</u>	<u>DIKE</u>
Identification No.:	CT 00203	CT 01712
Name of Dam:	Spaulding Pond Brook Site No.2 - Dam	Spaulding Pond Brook Site No.2 - Dike
Town:	Norwich	Norwich
County and State:	New London, Connecticut	New London, Connecticut
Stream:	Spaulding Pond Brook	Spaulding Pond Brook
Owner:	City of Norwich	City of Norwich
Date of Inspection:	8 April 1981	8 April 1981

BRIEF ASSESSMENT

Dam No.2 along Spaulding Pond Brook is an earth embankment structure. It is 12 feet wide at the crest, 200 feet long and 16 feet high. Both the upstream and downstream slopes are about 3H:1V. There is partial riprap protection on the upstream slope. The principal spillway consists of a reinforced concrete drop inlet structure with trash racks and a 30 inch diameter reinforced concrete pipe. There is a grassed emergency spillway 100 feet wide in the left abutment. A dike approximately 900 feet long surrounds the reservoir on the easterly side. The maximum height of this earth embankment dike is 15 feet. The dam is located downstream from Spaulding Pond Dam No.1 on the Spaulding Pond Brook. The maximum storage capacity of this facility is 63 acre feet at the level of the top of the dam, and its drainage area is approximately 0.45 square miles. The dam is a single purpose flood prevention dam which is intermittently used in the winter months for ice skating. It was constructed in 1968 by the City of Norwich with the assistance of the Soil Conservation Service.

As a result of the visual inspection, hydrologic and hydraulic computations and the review of the design plans and specifications, the dam is considered to be in GOOD condition. To assure the long term performance of this structure a few items of concern require attention. Most of these are maintenance items and include the restoration of the surface along the

crest of the dam, removing brush and debris from the culvert under the road and from the outlet channel, and cleaning debris from a drain outlet at the base of the dike.

The dam is classified as SMALL in size and as a HIGH hazard potential structure in accordance with the recommended guidelines established by the Corps of Engineers.

The test flood for these conditions ranges from half the Probable Maximum Flood to the Probable Maximum Flood ($\frac{1}{2}$ PMF to PMF). The test flood chosen for this dam, based on its size, is half the Probable Maximum Flood ($\frac{1}{2}$ PMF). This test flood has an inflow and outflow discharge equal to 400 cfs and will not overtop the dam. The emergency spillway together with the principal spillway is capable of handling 700% of the test flood outflow. It is recommended that the owner perform the remedial measures mentioned above and listed under Section 7 of this report.

The above recommendations should be instituted within two years of the owner's receipt of this report.

LENARD & DILAJ ENGINEERING, INC.



By:

John F. Lenard

John F. Lenard, P.E., President

Michael Dilaj

Michael Dilaj, P.E., Vice President
Project Manager



Dike-CT-01712


This Phase I Inspection Report on Spaulding Pond Brook Site No.2 Dam -CT-00203 has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgement and practice, and is hereby submitted for approval.



JOSEPH W. FINEGAN, JR. MEMBER
Water Control Branch
Engineering Division




ARAMAST MAHTESIAN, MEMBER
Geotechnical Engineering Branch
Engineering Division



CARNEY M. TERZIAN, CHAIRMAN
Design Branch
Engineering Division

APPROVAL RECOMMENDED:



JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I Investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I Investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigations, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I Investigation. However, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions will be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established Guidelines, the spillway test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonably possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and downstream damage potential.

The Phase I Investigation does not include an assessment of the need for fences, gates, no-trespassing signs, repairs to existing fences and railings and other items which may be needed to minimize trespass and provide greater security for the facility and safety to the public. An evaluation of the project for compliance with OSHA rules and regulations is also excluded.

TABLE OF CONTENTS

	<u>Page No.</u>
LETTER OF TRANSMITTAL	
BRIEF ASSESSMENT	
REVIEW BOARD PAGE	
PREFACE	i
TABLE OF CONTENTS	ii
OVERVIEW PHOTO	v
LOCATION MAP	vi

REPORT

SECTION 1 - PROJECT INFORMATION

1.1 General	1
a. Authority	
b. Purpose of Inspection Program	
c. Scope of Inspection Program	
1.2 Description of Project	2
a. Location	
b. Description of Dam and Appurtenances	
c. Size Classification	
d. Hazard Classification	
e. Ownership	
f. Operator	
g. Purpose of Dam	
h. Design and Construction History	
i. Normal Operational Procedure	
1.3 Pertinent Data	4
a. Drainage	
b. Discharge at Dam Site	
c. Elevations	
d. Reservoir Length	
e. Storage	
f. Reservoir Surface Area	
g. Dam	
h. Diversion and Regulating Tunnel	
i. Spillway	
j. Regulating Outlet	

	<u>Page No.</u>
SECTION 2 - ENGINEERING DATA	
2.1 Design	8
2.2 Construction	8
2.3 Operation	8
2.4 Evaluation	8
a. Availability	
b. Adequacy	
c. Validity	
SECTION 3 - VISUAL INSPECTION	
3.1 Findings	9
a. General	
b. Dam	
c. Appurtenant Structures	
d. Reservoir Area	
e. Downstream Channel	
3.2 Evaluation	11
SECTION 4 - OPERATIONAL AND MAINTENANCE PROCEDURES	
4.1 Operational Procedures	12
a. General	
b. Description of any Warning System in Effect	
4.2 Maintenance Procedures	12
a. General	
b. Operating Facilities	
4.3 Evaluation	12
SECTION 5 - EVALUATION HYDRAULICS/ HYDROLOGIC FEATURES	
5.1 General	13
5.2 Design Data	13
5.3 Experience Data	14

	<u>Page No.</u>
5.4 Test Flood Analysis	14
5.5 Dam Failure Analysis	15
SECTION 6 - EVALUATION OF STRUCTURAL STABILITY	
6.1 Visual Observation	16
6.2 Design and Construction Data	16
6.3 Post Construction Changes	16
6.4 Seismic Stability	16
SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES	
7.1 Dam Assessment	17
a. Condition	
b. Adequacy of Information	
c. Urgency	
7.2 Recommendations	17
7.3 Remedial Measures	17
a. Operating and Maintenance Procedures	
7.4 Alternatives	18

APPENDICES

APPENDIX A - INSPECTION CHECKLIST

APPENDIX B - ENGINEERING DATA

APPENDIX C - PHOTOGRAPHS

APPENDIX D - HYDROLOGIC AND HYDRAULIC COMPUTATIONS

APPENDIX E - INFORMATION AS CONTAINED IN THE NATIONAL
INVENTORY OF DAMS



OVERVIEW PHOTO


US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM MASSACHUSETTS

LENARD DILAJ ENGINEERING, INC.
STORRS CONNECTICUT
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

SPAULDING POND DAM #2
NORWICH, CONNECTICUT

CT 00203
MAY 1981



PHASE I INSPECTION REPORT

SECTION I - PROJECT INFORMATION

1.1 General:

- a. Authority: Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of Dam Inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Lenard & Dilaj Engineering, Inc. has been retained by the New England Division to inspect and report on selected dams in the States of Connecticut and Rhode Island. Authorization and notice to proceed were issued to Lenard & Dilaj Engineering, Inc. under a letter of 6 November, 1980 from William E. Hodgson, Jr., Colonel, Corps of Engineers. Contract No. DACW33-81-C-0014 has been assigned by the Corps of Engineers for this work.
- b. Purpose of Inspection Program: The purposes of the program are to:
 1. Perform technical inspection and evaluation of non-federal dams to identify conditions requiring correction in a timely manner by non-federal interest.
 2. Encourage and prepare the states to quickly initiate effective dam inspection programs for non-federal dams.
 3. To update, verify and complete the National Inventory of Dams.
- c. Scope of Inspection Program: The scope of this Phase I inspection report includes:
 1. Gathering, reviewing and presenting all available data as can be obtained from the owners, previous owners, the state and other associated parties.
 2. A field inspection of the facility detailing the visual condition of the dam, embankments and appurtenant structures.

3. Computations concerning the hydraulics and hydrology of the facility and its relationship to the calculated flood through the existing spillway.
4. An assessment of the condition of the facility and corrective measures required.

It should be noted that this report does not pass judgment on the safety or stability of the dam other than on a visual basis. The inspection is to identify those features of the dam which need corrective action and/or further study.

1.2 Description of the Project:

- a. Location: The project is located on Spaulding Pond Brook (a tributary to the Shetucket River) in the City of Norwich, County of New London, and State of Connecticut. The dam is located approximately 200 feet north of Mohegan Park Road, 7,000 feet upstream of the Shetucket River, and is shown on the Norwich, Connecticut USGS quadrangle map, having coordinates $41^{\circ} 32' 22''$ (north latitude) and $72^{\circ} 04' 06''$ (west longitude).
- b. Description of Dam and Appurtenances: Spaulding Pond Brook Dam No. 2 is an earth embankment dam 200 feet long and 16 feet high, with an average crest width of 12 feet. Both the upstream and downstream embankments have a slope of about 3H:1V. There is partial riprap protection on the upstream slope to a height of 6 to 7 feet. The riprap consists of large stones up to 4 and 5 feet in diameter. On the downstream slope, riprap protection is only provided near the outlet pipe. The small impoundment behind the dam is approximately 2 acres in size and 3 feet deep (see Photo 3).

Its principal spillway consists of a drop inlet structure located on the upstream slope of the dam. There is a low level outlet at the invert of the 30 inch pipe passing through the dam, controlled by a gate valve, and there are two additional inlets at higher elevations. A low level orifice, 12"x 20" in size, maintains normal water level at elevation 159.0 feet, while a high level intake on both sides of the structure with a total length of 15 feet will pass flood flows at an elevation of 166.3 feet. Any flows in addition to those that the 30 inch pipe could handle would pass over the 100 foot wide emergency spillway on the left side of the dam (see Site Plan and plates in Appendix B). Further left of the dam is a dike, about 900 feet long, with a maximum height of 15 feet and side slopes of 3H:1V. A nature

trail passing between the dam and dike divides the available storage into two separate areas. To maintain some equalization of water levels and flows, an arch culvert, 50" x 31" in size, passes beneath the road between these two reservoir areas.

- c. Size Classification: SMALL - With the pool level at the top of the dam, the impoundment capacity is 63 acre feet. The dam's height above the spillway pipe is 16 feet. On the basis of storage, it is therefore classified as a SMALL structure in accordance with the recommended guidelines of the Corps of Engineers, which state that a small dam is one whose storage is greater than or equal to 50 and less than 1,000 acre feet and whose height is greater than or equal to 25 and less than 40 feet.
- d. Hazard Classification: HIGH - The dam and dike are classified as having a HIGH hazard potential because they are located in an area where the failure discharge from either the dam or dike could cause the possible loss of more than a few lives and appreciable damage to property. The breach of the dam could cause damage to homes located 2,500 feet downstream from the dam. At this point no flooding is anticipated within the homes prior to failure, while post failure depths would be 2 to 3 feet above the sill elevations of most houses in the area. The breach of the dike would cause damage at homes located about 600 feet downstream. At this point no flow is anticipated prior to failure, while post failure depths would be about 2 feet above the sill elevation of the houses in the area.
- e. Ownership: Spaulding Pond Brook Dam No.2 is owned by the City of Norwich.
- f. Operator: Operation of this facility is under the supervision of the Department of Public Works, Walter J. Wadja, Jr., Director, City Hall, City of Norwich, Norwich, Connecticut, telephone 887-5413. Routine work at the dam is supervised by the Superintendent of Parks and Cemeteries.
- g. Purpose of Dam: Dam No. 2 along Spaulding Pond Brook is a flood water retarding dam. During the winter it is used for ice skating.
- h. Design and Construction History: Spaulding Pond Brook Dam No.2 was designed by the United States Department of Agriculture, Soil Conservation Service, Project No. CN-425-P, in 1966. It was built under the Watershed Protection and Flood Prevention Act by the City

of Norwich, State of Connecticut and New London County Soil and Water Conservation District with the assistance of the Soil Conservation Service of the United States Department of Agriculture in 1968.

- i. Normal Operating Procedures: Water level is normally maintained at the elevation of the low level orifice on the principal spillway drop inlet structure. Because it is a single purpose flood prevention dam, water is kept at a relatively low level in the pond by the low level inlet. Flood waters would enter the inlet structure at the high level crest of the riser. Since its construction, however, no flow has reached this level.

1.3 Pertinent Data:

- a. Drainage Area: Dam No.2 along Spaulding Pond Brook and its drainage area are located in New London County in southeastern Connecticut. The basin is irregular in shape and the entire watershed is only 0.45 square miles in size. Of this, 0.24 square miles are controlled by Dam No.1 at Spaulding Pond. The remaining area of 0.21 square miles contributes directly to Dam No.2. The topography is characterized by hilly terrain with elevations ranging from a high of 390 feet at the northern most point of the watershed to a low of 159 feet at the low level orifice of the inlet structure at the dam. Basin slopes are generally moderate with few steep areas. The storage available at Dam No.1 has a significant impact on the flow anticipated at the project area, as evident from the calculations attached in Appendix D of this report.

- b. Discharge at Damsite: Discharge at the dam is through the low level gated outlet, the low level orifice, the main riser crest, and over the emergency spillway. There are no other outlets along the dike. Most data shown below is taken from SCS design data and some has been calculated or interpolated therefrom.

1. Outlet works
 - Size: 30" RCP low level outlet
 - Invert Elev.: 156.0 feet
 - Discharge capacity: 80 cfs (at test flood level)
2. Maximum known flood at dam site:
 - Elevation of 164.3+ attained on January 26, 1978. Approximate discharge through dam - 18 cfs
3. Ungated spillway capacity at top of dam: 2,850 cfs at Elev. 172.3

4. Ungated spillway capacity
at test flood elevation: 400 cfs at Elev. 169.0
5. Gated spillway capacity
at normal pool elevation: N/A
6. Gated spillway capacity at
test flood elevation: N/A
7. Total spillway capacity
at test flood level: 400 cfs at Elev. 169.0
8. Total project discharge
at top of dam: 2,850 cfs at Elev. 172.3
9. Total project discharge
at test flood elevation: 400 cfs at Elev. 169.0

c. Elevations (Feet above National Geodetic Vertical Datum):

1. Streambed at toe of dam: 156.3
Toe of Dike: 157.2
2. Bottom of cutoff: 156 (Dam)
152 (Dike)
3. Maximum tailwater: N/A
4. Normal pool: 159.0
5. Full flood control pool: 168.1
6. Spillway crest: 166.3 (Principal)
168.1 (Emergency)
7. Design surcharge
(Original Design): 170.3
8. Top of dam: 172.3
9. Test flood surcharge: 169.0

d. Reservoir Length (in Feet):

1. Normal pool: 300
2. Flood control pool: 700
3. Spillway crest pool: 450 (Principal)
700 (Emergency)
4. Top of dam: 1,000
5. Test flood pool: 750

e. Storage (Acre Feet):

1. Normal pool:	4
2. Flood control pool:	33
3. Spillway crest pool:	25 (Principal) 33 (Emergency)
4. Top of dam:	63
5. Test flood pool:	40

f. Reservoir Surface Area (Acres):

1. Normal pool:	2.5
2. Flood control pool:	5.5
3. Spillway crest:	4.5 (Principal) 5.5 (Emergency)
4. Test flood pool:	5
5. Top of dam:	8.5

g. Dam and Dike:

	<u>Dam</u>	<u>Dike</u>
1. Type:	Earth embankment	Earth embankment
2. Length:	200 feet	900 feet
3. Height:	16 feet	15 feet
4. Top width:	12 feet	12 feet
5. Side slopes:	3H:1V	3H:1V
6. Zoning:	Core-Impervious Outer fill-Pervious	Core-Impervious Outer fill-Pervious
7. Impervious Core:	Silty sands from borrow material	Silty sands from borrow material
8. Cutoff:	To bedrock or limits of excavation	To bedrock or limits of excavation
9. Grout curtain:	None	None
10. Other:	Toe drains - two outlets	Toe drains - three outlets

h. Diversion and Regulating Tunnel: None

i. <u>Spillway (Principal):</u>	<u>Low Level</u>	<u>High Level</u>
1. Type:	12"x20" orifice in concrete wall	Concrete drop inlet
2. Length of weir:	1.7 feet	15 feet
3. Crest elevation:	159.0 feet	166.3 feet
4. Gates:	None	None
5. Upstream channel:	N/A	N/A
6. Downstream channel:	30" RCP to discharge point	30" RCP to discharge point
7. General:	N/A	N/A

Spillway (Emergency):

1. Type:	Grass channel
2. Length of crest:	100 feet
3. Crest elevation:	168.1 feet
4. Gates:	None
5. Upstream channel:	Grass slope
6. Downstream channel:	Grass slope
7. General:	Berm between dam and spillway to channel flow away from toe of dam.

j. Regulating Outlets:

1. Invert:	156.0 feet
2. Size:	12 inch diameter opening in concrete chamber
3. Description:	Opening in wall of riser on upstream side.
4. Control mechanism:	Hand wheel sluice gate lift
5. Other:	None

SECTION 2

ENGINEERING DATA

- 2.1 Design: Spaulding Pond Brook Dam No.2 was designed in 1966 by the United States Department of Agriculture, Soil Conservation Service, Engineering and Watershed Planning Unit, Upper Darby, Pennsylvania. The design report, design calculations, subsurface data, construction plans and specifications are available at the Soil Conservation Service office in Storrs, Connecticut. Selected calculations, plans and other data are reproduced in the Appendix of this report.
- 2.2 Construction: The entire facility was constructed in 1968. Construction supervision reports are available at the Soil Conservation Service.
- 2.3 Operation: Spaulding Pond Brook Dam No.2 was constructed for flood water retarding purposes. Other than routine maintenance, there is no operation involved. The facility is maintained by the City of Norwich Department of Public Works. Mowing and all other maintenance is accomplished by the City of Norwich Public Works Department.
- 2.4 Evaluation:
- a. Availability: The facility is open to the public at all hours. Consequently, it was made available for visual inspection. All design plans and calculations were made available for this review, and the more significant parts are reproduced in this report.
 - b. Adequacy: The detailed design information was found to be very adequate for making this review. The design report and the plans were found to be precise and thorough.
 - c. Validity: The plans made available were stamped "As Built" by the Soil Conservation Service. A field survey conducted at the site during the inspection confirmed that these plans were valid.

SECTION 3

VISUAL INSPECTION

3.1 Findings:

- a. General: An inspection of Spaulding Pond Brook Dam No.2 was performed on April 8, 1981 by Lenard & Dilaj Engineering, Inc. with the assistance of Geotechnical Engineers, Inc. The weather was clear and the temperature was about 60°F. At the time of inspection, the water level in the pond was 159.4 feet, about 0.4 feet above the orifice invert elevation.

On the basis of the visual inspection, the dam was judged to be in good condition.

- b. Dam: The dam is an earth embankment with 3H:1V upstream and downstream slopes. The crest width is about 12 feet. There is an emergency spillway that was excavated at the left abutment and a combination drop inlet spillway and gated low-level inlet structure near the center of the dam. The facility was constructed in 1968 by the City of Norwich with the assistance of the Soil Conservation Service, U.S. Department of Agriculture.
1. Crest: The crest of the dam is grass covered, but has been deteriorated by a foot and vehicle path. Runoff water has further accelerated this erosion process, as shown on Photo 2. The surface along the crest of the dam does not have a crown and thus water does not run off.
 2. Upstream Slope: The upstream slope is protected with riprap up to an elevation of 11 feet below the crest. Above this elevation, the slope is covered with long grasses. The riprap is in good condition, and above the riprap level there are no signs of erosion or sloughing.
 3. Downstream Slope: The downstream slope is covered with long grasses. There is no indication of seepage, erosion or sloughing because the water level in the pond is normally low. The design drawings show a longitudinal foundation drain under about the midpoint of the downstream slope. Two 8-inch corrugated metal pipes constitute the outlets for the drain and are located at both sides

of the drop inlet spillway outlet pipe. The left drain pipe is discharging about 6 gallons per hour, while the right drain discharges about 12 gallons per hour. The discharge of the left drain pipe is rust colored (Photo 7) while the discharge of the right drain pipe is clear. No seepage was observed at the downstream toe or further downstream of the dam.

- c. Appurtenant Structures: The appurtenant structures of this dam are the combination drop inlet spillway and gated low-level inlet structure, the emergency spillway and the dike.
1. Drop Inlet Spillway: The concrete structure and the trash racks are in good condition (Photo 4). There is a gate controlling a low-level inlet on the upstream face of the concrete structure (Photo 4). At the time of inspection, the gate was partially open. The outlet pipe discharges into a riprap-lined channel (Photo 7). There is some brush growing in the channel which may present some obstruction to the flow.
 2. Emergency Spillway: The emergency spillway is a 100 foot wide earth channel in the left abutment. The slopes and bottom of the channel are grass covered with no signs of erosion. A foot-path crosses the channel with insignificant erosion. The emergency spillway can be seen on the left side of Photo 3.
 3. Dike: The dike is an earth embankment with 3H:1V slopes. The drawings show that the dike has a longitudinal foundation drain under about the mid-point of the downstream slope. At the time of inspection, there was no water stored immediately upstream of the dike except for some standing water at about Sta 14+50. The dike crest and slopes are grass covered with no significant erosion, except for ruts left by vehicles along the crest (Photo 9). The foundation drain has three outlets (numbered 3, 4, and 5 in the design drawings). Two of the three outlets, 3 and 5, do not contain a pipe, but consist of a trench filled with granular material covered by riprap at their exit at the toe of the dike. At the time of inspection, these two outlets were not discharging. The third outlet, at Sta 14+50, consists of an 8 inch corrugated metal pipe that was discharging a small flow, as evidenced by the wet area at the end of the pipe. The pipe was buried under stones and debris (Photo 10).

Seepage was observed at the toe of the dike in the vicinity of the drain pipe probably as the result of the blockage of the pipe.

- d. Reservoir Area: The reservoir is crossed by a road consisting of earth fill with a corrugated metal pipe culvert beneath it, which has been partially silted up (Photos 5 and 6). The road earth fill also supports a natural gas pipeline.
 - e. Downstream Channel: The downstream channel for the outlet pipe is riprap protected and has some brush growth. The emergency spillway discharges into the outlet channel about 200 feet downstream of the dam. The downstream channel then crosses under Mohegan Park Road through a 24 inch diameter culvert (Photo 8).
- 3.2 Evaluation: On the basis of the visual inspection, the dam and its appurtenant structures are judged to be in good condition. Items requiring maintenance consist of:
- a. brush removal in the outlet channel,
 - b. removal of debris from the No.4 drain outlet of the dike (Sta 14+50),
 - c. repair of erosion along the crest of the dam and dike,
 - d. cleaning of the culvert under the road (and gas line) crossing through the reservoir. This is necessary to maintain a flow to equalize water levels within the reservoir behind the dam and the dike.
 - e. The reservoir was not storing flood waters at the time of inspection; thus, no determination of seepage problems could be made. An attempt should be made to inspect the downstream slopes of the dam and dike during periods of high water levels in the reservoir.

SECTION 4

OPERATIONAL AND MAINTENANCE PROCEDURES

4.1 Operational Procedure:

- a. General: The City of Norwich Public Works Department operates the dam and appurtenant facilities. The primary purpose of this facility is to provide for flood protection. For this reason water is always kept at a low elevation. The second orifice of the principal spillway, three feet above the bottom of the reservoir, is always open. Consequently, water levels are always maintained at this elevation, unless large flood flows result in a temporary rise in the pond level. During the winter months the pond is used for ice skating by local residents. There are no operational procedures in effect at the dam. According to reports, the emergency spillway has never been used.
- b. Description of Any Warning System in Effect: Emergency action and/or warning is coordinated by the City of Norwich Department of Public Works. No formal emergency or contingency plan is in effect. In a letter dated August 30, 1968, the Soil Conservation Service did, however, suggest that "the park roads be closed when there is continuing intensive rainfall following rainfall of 3 to 4 inches within two hours, or when the flood pool is 1.2 feet below the top of the inlet riser (site 2) and still rising."

4.2 Maintenance Procedures:

- a. General: Routine maintenance is carried out and is supervised by the Superintendent of Parks and Cemeteries. The grassed areas are periodically mowed.
- b. Operating Facilities: The only operating facility is the principal spillway. The construction of the inlet structure reduces the necessity for frequent maintenance. There does not seem to be any need for maintenance on the operating facilities other than intermittent repair as the need arises and occasional discharge of accumulated sediments in the pond.

- 4.3 Evaluation: Maintenance of the dam and appurtenant facilities needs to be improved. A formal program of operation and maintenance procedures should be implemented, including documentation to provide complete records for future reference; a formal downstream warning system should be developed and implemented; and a program of biennial technical inspections by a qualified registered engineer should be instituted.

SECTION 5

EVALUATION OF HYDRAULIC/HYDROLOGIC FEATURES

- 5.1 General: Spaulding Pond Brook Dam No.2 is an earth embankment dam. It is 200 feet long, 12 feet wide at the crest, and 16 feet high above streambed. Its principal spillway consists of a drop inlet structure located on the upstream slope of the dam. There is a low level outlet at the invert of the 30 inch pipe passing through the dam, controlled by a gate valve, and there are two additional inlets at higher elevations. A low level orifice maintains normal water level at elevation 159.0 feet, while a high level intake on both sides of the structure will pass flood flows at an elevation of 166.3 feet. Any flows in addition to those that the 30 inch pipe could handle would pass over the 100 foot wide emergency spillway on the left side of the dam. Further left of the dam is a dike about 900 feet long with a maximum height of 15 feet. A wood road passing between the dam and dike divides the available storage into two separate areas. To maintain some equalization of water levels and flows, an arch culvert passes beneath the road between these two reservoir areas.

The channel immediately downstream of the dam is a riprap lined excavation. Prior to crossing the road through a 24 inch pipe culvert, it is a natural streambed. After passing beneath the road, the brook flow passes through a small wetland area and is then channeled through a long series of pipes through the residential and downtown areas of Norwich, before discharging into the Shetucket River near its intersection with the Thames River.

The total watershed covers an area of 0.45 square miles. The upper area of 0.24 square miles is controlled by Spaulding Pond Brook Dam No.1. The portion contributing directly to Spaulding Pond Brook Dam No.2 consists of 0.21 square miles. It should be noted that a portion of the lower watershed area has been added on by the construction of a diversion ditch by the SCS located just to the left of the dike. This is not apparent from USGS quadrangle maps.

At the riser crest elevation of 166.3 feet, available storage at the site is approximately 25 acre feet. This increases to 40 acre feet at the test flood level and 63 acre feet at the top of the dam.

- 5.2 Design Data: Sufficient design data was found to be available from records of the Soil Conservation Service. Design

calculations, plans, inspection reports, and as-built drawings are on file both at the State and SCS offices.

A summary of the available design data includes the following:

Drainage Area:	132 acres
Time of Concentration:	0.5 hours
Emergency Spillway	
- Frequency of use:	Once in 100 years
- Duration of flow through spillway:	8.8 hours
- Maximum velocity at control section:	6.9 ft./sec.
Earth Fill	
- Height:	16 feet
- Volume:	18,500 C.Y.

<u>Flood Frequency or Determining Factor</u>	<u>Elev. (Ft.)</u>	<u>Storage (Ac.Ft.)</u>	<u>Inflow (cfs)</u>	<u>Outflow (cfs)</u>
50 yr.	159.0	0.9	-	20.9
100 yr.-6 hr. AMC II	166.3	24.0	205	84
100 yr. -6 hr. AMC III	167.6	30.2	367	75
16.5 in. rainfall AMC III	170.3	47.6	1,312	1,094
Design high water plus 2 ft.	172.3	54.2	1,928	1,760

5.3 Experience Data: While no day to day records are maintained for the facility, it is known that since its construction, no flow has passed over the principal spillway crest or through the emergency spillway. The highest water level, attained on January 26, 1978, is marked on the side of the riser (Photo No.4) at elevation 164.3 feet, 2 feet below the crest elevation of the inlet structure and 4 feet below the crest of the emergency spillway.

5.4 Test Flood Analysis: Based on the "Recommended Guidelines for Safety Inspection of Dams," Spaulding Pond Brook Dam No.2 is classified as SMALL in size and as having a HIGH hazard potential. The test flood for these conditions ranges from half the Probable Maximum Flood to the Probable Maximum Flood ($\frac{1}{2}$ PMF to PMF). Based on the size of the dam and its storage capacity, the $\frac{1}{2}$ PMF was chosen as the test flood.

Using the HEC-1 Flood Hydrograph Computer Program developed by the Army Corps of Engineers for dam safety investigations, the inflow and outflow for the test flood were both found to be 400 cfs (900 CSM). As a basis for comparison, the PMF resulted in an inflow and outflow of 1,350 cfs (3,000 CSM). The outflow capacity of the dam with water level at the top of its crest is 2,850 cfs, which is equivalent to 700% of the routed test flood outflow. The free-board distance remaining between the high water level of the test flood and the top of the dam would be about 3.3 feet. Because the dam at Site No.2 is the second in a series of flood control structures along Spaulding Pond Brook, the flood was also routed through Dam Site No.1 to take advantage of available storage at that site.

- 5.5 Dam Failure Analysis: A dam failure analysis was performed using the "Rule of Thumb" method for estimating downstream dam failure hydrographs, as developed by the Corps of Engineers. Peak outflow before failure of the dam would be 400 cfs, producing a depth of flow of about 0.5 feet at the initial impact area (an apartment complex) 1,000 feet downstream of the dam and a depth of 2.0 feet at a housing area 2,500 feet downstream. The calculated dam failure discharge, based on an assumed breach width of 50 feet, is 5,200 cfs, which will produce a depth of flow of 2.1 feet and 4.9 feet at the same downstream points. Pool elevation at the time of the breach was assumed to be at the level of the $\frac{1}{2}$ PMF. This means an increase in the depth of flow of 1.6 feet and 3 feet, due to the failure of the dam. At the second point downstream of the dam (25+00), the increase of 3 feet in water level will mean a rise of 2 to 3 feet above the sill elevation of homes in that area. The analysis covered a distance of 4,500 feet downstream of the dam, as shown by the calculations in Appendix D. Through its entire length, this flow would pass through densely populated residential and commercial areas of Norwich. The breach of the dam could cause significant downstream damage with the possible loss of more than a few lives.

For the dike, there would be only a negligible flow preceding the failure. The calculated dike failure discharge of 9,770 cfs, based on an assumed breach width of 100 feet, would produce a depth of flow of 2.3 feet at a housing development about 600 feet downstream of the dike. This means an increase in flow from a negligible depth before failure to a depth of 2.3 feet after failure of the dike. This increase in water depth can cause houses in this development to be flooded with about 2 feet of water above the sill elevation, and thereby cause the possible loss of more than a few lives. As shown on the map of the Potential Flood Area of the dam and dike failures, the impact area of the dike initially differs from that of the dam. About 2,000 feet downstream, however, the two impact areas converge.

Based on the failure analyses of both the dam and dike, these structures are classified as having a HIGH hazard potential.

SECTION 6

EVALUATION OF STRUCTURAL STABILITY

- 6.1 Visual Observations: The visual inspection did not reveal any indications of structural instability.
- 6.2 Design and Construction Data: The design and construction data consists of exploration data, design notes, plans and as-built drawings prepared by the U.S. Soil Conservation Service. For a formal stability analysis additional data would be required.
- 6.3 Post Construction Changes: There are no known or observed post construction changes.
- 6.4 Seismic Stability: Spaulding Pond Brook Dam No.2 is located in Seismic Zone 1 and, in accordance with the Phase I inspection guidelines, does not warrant seismic stability analysis.

SECTION 7

ASSESSMENT, RECOMMENDATIONS, AND REMEDIAL MEASURES

7.1 Dam Assessment:

- a. Condition: The visual inspection indicated that the dam and its appurtenant structures were in good condition. There are some items requiring maintenance:
 - 1. Brush removal in the outlet channel.
 - 2. Removal of debris from No.4 drain outlet of the dike (Sta 14+ 50).
 - 3. Repair of erosion at the crest of the dam and dike.
 - 4. Cleaning of the culvert under the road crossing through the reservoir.
- b. Adequacy of Information: The assessment of the condition of the dam is based on a review of existing drawings and the visual inspection.
- c. Urgency: The remedial measures described below should be implemented by the owner within one year of receipt of this report.

7.2 Recommendations: The following recommendations should be implemented under the direction of a qualified registered professional engineer.

- a. The downstream slopes of the dam and dike should be inspected during periods of high water levels in the reservoir.

7.3 Remedial Measures:

- a. Operating and Maintenance Procedures:
 - 1. Remove brush from outlet channel.
 - 2. Remove debris from No.4 drain outlet of the dike.
 - 3. Repair erosion at crest of dam and dike.
 - 4. Clean culvert under road crossing the reservoir.
 - 5. Institute a program of biennial technical inspections by a qualified registered professional engineer.

6. Develop a formal warning system for downstream inhabitants to be used in case of emergencies.
 7. Monitor the project during and immediately after periods of intense rainfall and check for possible seepage. Keep a record of flood pool levels for future reference purposes.
- 7.4 Alternatives: There are no practical alternatives to the above recommendations.

APPENDIX A

INSPECTION CHECKLIST

VISUAL INSPECTION CHECKLIST
PARTY ORGANIZATION

PROJECT SPAULDING POND DAM #2

DATE April 8, 1981

TIME 9 am - 12 noon

WEATHER Clear, 60's

W.S. ELEV. _____ U.S. _____ DN.S. _____

PARTY:

- | | |
|-----------------------------------------|------------------------------------|
| 1. <u>John Lenard - L.D.E.I.</u> | 6. <u>Karl Acimovic - L.D.E.I.</u> |
| 2. <u>Michael Dilaj - L.D.E.I.</u> | 7. _____ |
| 3. <u>Michael Romanowski - L.D.E.I.</u> | 8. _____ |
| 4. <u>Mark Vasington - L.D.E.I.</u> | 9. _____ |
| 5. <u>Gonzalo Castro - G.E.I.</u> | 10. _____ |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Geotechnical</u>	<u>Gonzalo Castro</u>	
2. <u>Structural, Civil</u>	<u>John Lenard</u>	
3. <u>Hydraulics, Hydrology</u>	<u>Karl Acimovic, Michael Dilaj</u>	
4. <u>Survey, Civil</u>	<u>Michael Romanowski</u>	
5. <u>Survey</u>	<u>Mark Vasington</u>	
6. _____		
7. _____		
8. _____		
9. _____		
10. _____		

PERIODIC INSPECTION CHECKLIST

PROJECT SPAULDING POND DAM DATE April 8, 1981
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<u>DAM EMBANKMENT</u>	
Crest Elevation	172.3 ft.
Current Pool Elevation	159.4 ft. (9 feet below top of inlet structure)
Maximum Impoundment to Date	To elevation 164.3 ft.
Surface Cracks	None observed.
Pavement Condition	Not applicable.
Movement or Settlement of Crest	None observed. Ruts due to vehicle and foot traffic.
Lateral Movement	None observed
Vertical Alignment	Too irregular to judge.
Horizontal Alignment	Too irregular to judge.
Condition at Abutment and at Concrete Structures	Good.
Indications of Movement of Structural Items on Slopes	None.
Trespassing on Slopes	Several footpaths, no significant erosion.
Sloughing or Erosion of Slopes or Abutments	None.
Rock Slope Protection - Riprap Failures	Large riprap below el. 161.5. Good condition.
Unusual Movement or Cracking at or Near Toe	None observed.
Unusual Embankment or Downstream Seepage	None observed.
Piping or Boils	None observed.
Foundation Drainage Features	Drainage trench. Two 8 inch outlet pipes discharging ~0.1 and 0.2 gpm.
Toe Drains	None known.
Instrumentation System	None known.
Vegetation	A-2 Grass, long. No trees or brush.

PERIODIC INSPECTION CHECKLIST

PROJECT SPAULDING POND DAM DATE April 8, 1981
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<u>DIKE EMBANKMENT</u>	
Crest Elevation	172.3 ft.
Current Pool Elevation	None
Maximum Impoundment to Date	To elevation 164.3 ft.
Surface Cracks	None observed.
Pavement Condition	Not applicable
Movement or Settlement of Crest	None observed. Ruts due to traffic.
Lateral Movement	None observed.
Vertical Alignment	Too irregular to judge.
Horizontal Alignment	Too irregular to judge.
Condition at Abutment and at Concrete Structures	Good.
Indications of Movement of Structural Items on Slopes	Not applicable.
Trespassing on Slopes	Several footpaths. No significant erosion.
Sloughing or Erosion of Slopes or Abutments	None observed.
Rock Slope Protection - Riprap Failures	No slope protection.
Unusual Movement or Cracking at or Near Toes	None observed.
Unusual Embankment or Downstream Seepage	Some apparent seepage at maximum section left of drainage outlet #4. Small head due to ponding of water upstream in low area. Generally dike is above water level. None observed.
Piping or Boils	
Foundation Drainage Features	Drainage trench three outlets. No discharge except drain #4.
Toe Drains	None known.
Instrumentation System	None known.
Vegetation	Grass, long. No bushes.

PERIODIC INSPECTION CHECKLIST

PROJECT SPAULDING POND DAM

DATE April 8, 1981

PROJECT FEATURE _____

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - INTAKE CHANNEL AND INTAKE STRUCTURE</u></p> <p>a. Approach Channel</p> <p>Slope Conditions</p> <p>Bottom Conditions</p> <p>Rock Slides or Falls</p> <p>Log Boom</p> <p>Debris</p> <p>Condition of Concrete Lining</p> <p>Drains or Weep Holes</p> <p>b. Intake Structure</p> <p>Condition of Concrete</p> <p>Stop Logs and Slots</p> <p>A-1</p>	<p>No approach channel.</p> <p>Good.</p> <p>Good.</p>

PERIODIC INSPECTION CHECKLIST

PROJECT SPAULDING POND DAM

DATE April 8, 1981

PROJECT FEATURE _____

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - CONTROL TOWER</u>	
a. Concrete and Structural	
General Condition	<i>Good.</i>
Condition of Joints	<i>Good.</i>
Spalling	<i>None observed.</i>
Visible Reinforcing	<i>None observed.</i>
Rusting or Staining of Concrete	<i>None observed.</i>
Any Seepage or Efflorescence	<i>None observed.</i>
Joint Alignment	
Unusual Seepage or Leaks in Gate Chamber	<i>None observed.</i>
Cracks	<i>None observed.</i>
Rusting or Corrosion of Steel	<i>None observed.</i>
b. Mechanical and Electrical	<i>Not applicable.</i>
Air Vents	
Float Wells	
Crane Hoist	
Elevator	
Hydraulic System	
Service Gates	
Emergency Gates	
Lightning Protection System	
Emergency Power System	
Wiring and Lighting System	

PERIODIC INSPECTION CHECKLIST

PROJECT SPAULDING POND DAM DATE April 8, 1981
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<u>OUTLET WORKS - TRANSITION AND CONDUIT</u>	
General Condition of Concrete	<i>Good.</i>
Rust or Staining on Concrete	<i>None observed.</i>
Spalling	<i>None observed.</i>
Erosion or Cavitation	<i>None observed.</i>
Cracking	<i>None observed.</i>
Alignment of Monoliths	<i>Not applicable.</i>
Alignment of Joints	<i>Not applicable.</i>
Numbering of Monoliths	<i>Not applicable.</i>

PERIODIC INSPECTION CHECKLIST

PROJECT SPAULDING POND DAM

DATE April 8, 1981

PROJECT FEATURE _____

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED

CONDITION

OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL

General Condition of Concrete

None

Rust or Staining

Spalling

Erosion or Cavitation

Visible Reinforcing

Any Seepage or Efflorescence

Condition at Joints

Drain holes

Channel

Good condition. Large riprap.

Loose Rock or Trees Overhanging
Channel

Not applicable.

Condition of Discharge Channel

Good. Some growth of brush.

PERIODIC INSPECTION CHECKLIST

PROJECT SPAULDING POND DAM

DATE April 8, 1981

PROJECT FEATURE _____

NAME _____

DISCIPLINE _____

NAME _____

AREA EVALUATED

CONDITION

OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS

a. Approach Channel

No approach channel.

General Condition

Loose Rock Overhanging Channel

Trees Overhanging Channel

Floor of Approach Channel

b. Weir and Training Walls

Open earth channel, grassy surface.

General Condition of Concrete

Not applicable.

Rust or Staining

Not applicable.

Spalling

Not applicable.

Any Visible Reinforcing

Not applicable.

Any Seepage or Efflorescence

Not applicable.

Drain Holes

Not applicable.

c. Discharge Channel

General Condition

Good, grass-covered.

Loose Rock Overhanging Channel

None.

Trees Overhanging Channel

None.

Floor of Channel

Grass.

Other Obstructions

None observed.

Other Comments

PERIODIC INSPECTION CHECKLIST

PROJECT SPAULDING POND DAM DATE April 8, 1981
 PROJECT FEATURE _____ NAME _____
 DISCIPLINE _____ NAME _____

AREA EVALUATED	CONDITION
<p><u>OUTLET WORKS - SERVICE BRIDGE</u></p> <p>a. Super Structure</p> <p>Bearings</p> <p>Anchor Bolts</p> <p>Bridge Seat</p> <p>Longitudinal Members</p> <p>Underside of Deck</p> <p>Secondary Bracing</p> <p>Deck</p> <p>Drainage System</p> <p>Railings</p> <p>Expansion Joints</p> <p>Paint</p> <p>b. Abutment & Piers</p> <p>General Condition of Concrete</p> <p>Alignment of Abutment</p> <p>Approach to Bridge</p> <p>Condition of Seat & Backwall</p>	<p><i>There is no service bridge.</i></p>

APPENDIX B

ENGINEERING DATA




Photo 1. Bronze plate at dam with project information.




Photo 2. Footpath and vehicle rut running along crest of dam. Note runoff erosion developing along path.

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

LENARD DILAJ ENGINEERING, INC.
STORRS, CONNECTICUT
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

SPAULDING POND DAM #2
NORWICH, CONNECTICUT

CT 00203

MAY 1981

C-2



Photo 3. View of dam from across reservoir on upstream side. Note emergency spillway depression on left side of photo.



Photo 4. Drop inlet primary spillway structure. Note grate for pipe inlet on upstream side.

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

LENARD-DILAJ ENGINEERING, INC.
STORRS, CONNECTICUT
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

SPAULDING POND DAM #2
NORWICH, CONNECTICUT

CT 00203

MAY 1981

C-3



Photo 5. Inlet side of culvert at the road between the dam and dike storage areas. Note small bush growing at invert and missing asphalt coating in the culvert.




Photo 6. Discharge side of same culvert. Note siltation and vegetation in flow path.

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

LENARD-DILAJ ENGINEERING, INC.
STORRS, CONNECTICUT
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

SPAULDING POND DAM #2
NORWICH, CONNECTICUT

CT 00203

MAY 1981

C-4



Photo 7. Outlet pipe of primary spillway at dam. Note foundation drains on both sides of outlet pipe and rust colored discharge from the left foundation drain.




Photo 8. Twenty-four inch corrugated metal culvert crossing the road below the dam.

US ARMY ENGINEER DIV. NEW ENGLAND
CORPS OF ENGINEERS
WALTHAM, MASSACHUSETTS

LENARD-DILAJ ENGINEERING, INC.
STORRS, CONNECTICUT
ENGINEER

NATIONAL PROGRAM OF
INSPECTION OF
NON-FED. DAMS

SPAULDING POND DAM #2
NORWICH, CONNECTICUT

CT 00203
MAY 1981

C-5



Photo 9. View of dike from left abutment.



Photo 10. Silted drain outlet No. 4 near center of dike.

US ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASSACHUSETTS	NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS	SPAULDING POND DAM #2 NORWICH, CONNECTICUT
LENARD DILAJ ENGINEERING, INC. STORRS, CONNECTICUT ENGINEER		CT 00203
MAY 1981		
		C-6

APPENDIX D

HYDROLOGIC AND HYDRAULIC
COMPUTATIONS

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPILLWAY PAIL LAY #2
SHEET NO 1 OF 1
CALCULATED BY K. A. DATE 4/22/51
CHECKED BY _____ DATE _____
SCALE _____

DETERMINATION OF SPILLWAY TEST FLOOD*

A. SIZE CLASSIFICATION

Based on either storage or height

THIS DAM:

<u>Small</u>	Storage 50-999 Ac.-Ft.	<u>54 AC.-FT.</u>
	Height 25-39 Ft.	<u>16 FT.</u>
Intermediate	Storage 1,000-50,000 Ac.Ft.	_____
	Height 40-100 Ft.	_____
Large	Storage More than 50,000 Ac.-Ft.	_____
	Height Greater than 100 Ft.	_____

B. HAZARD POTENTIAL CLASSIFICATION

<u>Category</u>	<u>Loss of Life</u>	<u>Economic Loss</u>
Low	None expected	Minimal
Significant	Few	Appreciable
<u>High</u>	<u>More than few</u>	<u>Excessive</u>
Hazard Classification <u>HIGH</u>		

C. HYDROLOGIC EVALUATION GUIDELINES

<u>Hazard</u>	<u>Size</u>	<u>Spillway Test Flood</u>
Low	Small	50 to 100-Year Frequency
	Intermediate	100-Year Frequency to $\frac{1}{2}$ PMF
	Large	$\frac{1}{2}$ PMF to PMF
Significant	Small	100-Year Frequency to $\frac{1}{2}$ PMF
	Intermediate	$\frac{1}{2}$ PMF to PMF
	Large	PMF
<u>High</u>	<u>Small</u>	<u>$\frac{1}{2}$ PMF to PMF</u>
	Intermediate	PMF
	Large	PMF

Spillway Test Flood $\frac{1}{2}$ PMF

* Based upon "Recommended Guidelines for Safety Inspection of Dams" Department of the Army, Office of the Chief of Engineers, November 1976.

LIMITS OF WATERSHED

DAM

LENARD-DILAJ ENGINEERING, INC. STORRS, CONNECTICUT ENGINEER		US ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASSACHUSETTS	
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS			
WATERSHED MAP			
SPAULDING POND DAM			
SITE #2			
NORWICH, CONNECTICUT			
DRAWN BY E.R.D.	CHECKED BY K.A.	APPROVED BY J.L.	SCALE DATE 1/14/54 SHEET

PREVIEW OF SEQUENCE OF STREAM NETWORK CALCULATIONS

RUNOFF HYDROGRAPH AT	1
ROUTE HYDROGRAPH TO	2
RUNOFF HYDROGRAPH AT	3
COMBINE 2 HYDROGRAPHS AT	4
ROUTE HYDROGRAPH TO	5
END OF NETWORK	

SPAULDING POND BROOK WATERSHED DAM NO.2

FLOOD HYDROGRAPH PACKAGE (HFC-1)
DAM SAFETY VERSION JULY 1978
LAST MODIFICATION 26 FEB 79

WURL DATED 05/07/81
TIME 0 12.35.10.

SPAULDING POND BROOK WATERSHED DAM NO. 2 NORWICH, CONNECTICUT
80-27-12
MAY 1981 DESIGN STORM --- 1/2 PMF

JOB SPECIFICATION
NG NHR NMIN IDAY IMR IMIN METRC IPLT IPRT NSTAN
150 0 30 0 0 0 0 0 4 0
JOPER NAT LROPI IMAGE
5 0 0 0 0

MULTI-PLAN ANALYSES TO BE PERFORMED

RII05= 10 20 30 50 80 100
NPLAN= 1 NRTIO= 6 LPTIO= 1

***** SUR-AREA RUNOFF COMPUTATION *****

CALCULATION OF INFLOW HYDROGRAPH TO SPAULDING POND DAM NO. 1

ISTAU	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
1	0	0	0	1	0	1	0	0

HYDROGRAPH DATA

IMYDG	IUMG	TAREA	SNAP	IMSDA	IMSPC	RATIO	ISNOW	ISAVE	LOCAL
1	1	26	0.00	26	0.00	0.000	0	0	0

PRECIP DATA

SPEE	RMS	W	W12	W24	P72	R96
0.00	25.20	100.00	111.00	120.00	127.00	0.00

TMSPC COMPUTED BY THE PROGRAM IS .800

LOSS DATA

LROPT	STPKD	DLTMR	RTIOL	EPAIN	STKKS	RTIOK	STHIL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	20	0.00	0.00

UNIT HYDROGRAPH DATA

TP= 1.38 CP= 0.3 N14= 0

RECESSION DATA

SIRIO= 1.80 LROCSN= 0.05 RTIOB= 1.00

UNIT HYDROGRAPH IS END-OF-PERIOD ORIGINATES, LAG= 1.37 HOURS, CP= .42 VOL= 1.00

1. 48. 3. 2. 1. 1. 20. 13. 9. 6.

SUM 25.60 20.02 5.59 8858.
(650.1(508.1(142.1(250.83)

.....

HYDROGRAPH ROUTING

ROUTED FLOWS THROUGH SPAULDING POND DAM NO.1

ISTAO	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
2	1	0	0	2	0	1	0	0

ROUTING DATA

GLSS	CLSS	AVG	IRES	TSAME	IOPT	IPMP	LSTR
0.0	0.000	0.00	1	1	0	0	0

NSIPS	NSTUL	LAG	AMSKK	X	TSK	STORA	ISPRAT
1	0	0	0.000	0.000	0.000	-241.	-1

STAGE	241.00	242.00	244.00	245.00	246.00	247.00	248.00
-------	--------	--------	--------	--------	--------	--------	--------

FLOW	0.00	10.00	15.00	25.00	80.00	250.00	780.00
------	------	-------	-------	-------	-------	--------	--------

SURFACE AREA= 13. 16.

CAPACITY= 0. 72.

ELEVATION= 241. 242.

CMEL	SPWID	COOW	EXPM	EVELL	COOL	CAREA	EXPL
241.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0

DAM DATA
IOPEL 250.5 COLO 2.6 EXPJ 1.5 DAMWID 1000.

PEAK OUTFLOW IS 223. AT TIME 43.00 HOURS


SPAULDING POND DAM NO.1

INFLOW/OUTFLOW HYDROGRAPH

4

STATION 2

INFLOW(I), OUTFLOW(O) AND OBSERVED FLOW(*)



[illegible]

..... SUR-AREA RUNOFF COMPUTATION

CALCULATION OF INFLOW HYDROGRAPH TO SPAULDING POND DAM NO.2

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
3	0	0	0	1	0	1	0	0

HYDROGRAPH DATA

IMYDG	IUNG	TAREA	SNAP	TRSDA	TRSPC	RATIO	ISNOW	ISAME	LOCAL
1	1	21	1.00	21	0.00	0.000	0	0	0

PRECIP DATA

SPEE	PWS	R6	R12	R24	R48	R72	R96
0.80	25.20	100.00	111.00	120.00	127.00	0.00	0.00

TRSPC COMPUTED BY THE PROGRAM IS .800

LOSS DATA

LROPT	STRKR	DLTKR	RTIOL	ERAIN	STRKS	RTIOK	STRIL	CNSTL	ALSMX	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	1.00	.20	0.00	0.00

UNIT HYDROGRAPH DATA

IP= 1.14 CP= .63 NIA= 0

RECESSION DATA

SIMIQ= 1.80 ORCSN= .05 RTIOP= 1.00

UNIT HYDROGRAPH 12 END-OF-PERIOD ORIGINATES. LAG= 1.14 HOURS. CP= .63 VOL= 1.00

17. 54. 70. 52. 31. 19. 11. 7. 4. 2.

1. 1.

END-OF-PERIOD FLOW

MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q	MO.DA	HR.MN	PERIOD	RAIN	EXCS	LOSS	COMP Q
0	0	0	0	0	0	0	0	0	0	0	0	0	0

SUM 25.60 20.02 5.59 7412.
(650.)(508.)(142.)(209.88)

.....

COMBINE HYDROGRAPHS

COMBINE HYDROGRAPHS 2 AND 3 INFLOW TO SPAULDING POND NO.2

ISTAQ	ICOMP	IECON	ITAPE	JPLT	JPRT	INAME	ISTAGE	IAUTO
4	2	0	0	1	0	1	0	0

HYDROGRAPH ROUTING

COMBINED INFLOW ROUTED THROUGH SPAULDING POND DAM NO.2

.....

ISTAO ICOMP IFCUN ITAPE JPLT JPRT INAME ISTAGE IAUTO

ROUTING DATA
QLOSS CLOSS AVG IRES ISAME IOPT IPMP LSTR

NSTPS NSTUL LAG AMSKK X TSK STORA ISPRAT

STAGE 159.00 160.00 162.00 164.00 166.00 168.00 170.00 171.70

FLOW 0.00 5.70 12.70 17.00 20.40 282.00 1344.00 2228.00

CAPACITY= 4. 8. 15. 23. 33. 45. 60. 80. 103.

ELEVATION= 160. 162. 164. 166. 168. 170. 172. 174. 176.

CMEL SPWID COOW EXPW ELEVEL COOL CAREA EXPL
159.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0

DAM DATA
TOPEL COGD EXPO DAMWID
172.3 2.8 1.5 780.

8

PEAK OUTFLOW IS 417. AT TIME 42.50 HOURS

SPAULDING POND DAM NO. 2

INFLOW/OUTFLOW HYDROGRAPH

STATION 5

INFLOW (I), OUTFLOW (O) AND OBSERVED FLOW (*)

0.	50.	100.	150.	200.	250.	300.	350.	400.	450.	0.	0.	0.	0.
1.00 210
1.30 310
1.60 410
2.00 510
2.30 610
2.60 710
3.00 810
3.30 910
3.60 1010
4.00 1110
4.30 1210
4.60 1310
5.00 1410
5.30 1510
5.60 1610
6.00 1710
6.30 1810
6.60 1910
7.00 2010
7.30 2110
7.60 2210
8.00 2310
8.30 2410
8.60 2510
9.00 2610
9.30 2710
9.60 2810
10.00 2910
10.30 3010
10.60 3110
11.00 3210
11.30 3310
11.60 3410
12.00 3510
12.30 3610
12.60 3710
13.00 3810
13.30 3910
13.60 4010
14.00 4110
14.30 4210
14.60 4310
15.00 4410
15.30 4510
15.60 4610
16.00 4710
16.30 4810
16.60 4910
17.00 5010
17.30 5110
17.60 5210
18.00 5310
18.30 5410
18.60 5510
19.00 5610
19.30 5710
19.60 5810
20.00 5910
20.30 6010
20.60 6110
21.00 6210
21.30 6310
21.60 6410
22.00 6510
22.30 6610
22.60 6710
23.00 6810
23.30 6910
23.60 7010
24.00 7110
24.30 7210
24.60 7310
25.00 7410
25.30 7510
25.60 7610
26.00 7710
26.30 7810
26.60 7910
27.00 8010
27.30 8110
27.60 8210
28.00 8310
28.30 8410
28.60 8510
29.00 8610
29.30 8710
29.60 8810
30.00 8910
30.30 9010
30.60 9110
31.00 9210
31.30 9310
31.60 9410
32.00 9510
32.30 9610
32.60 9710
33.00 9810
33.30 9910
33.60 10010

10

UNITED STATES GOVERNMENT

4.30 5710

5.30 5810

6.30 5910

7.30 6010

8.30 6110

9.30 6210

10.30 6310

11.30 6401

12.30 6501

13.30 6601

14.30 6701

15.30 6801

16.30 6901

17.30 7001

18.30 7101

19.30 7201

20.30 7301

21.30 7401

22.30 7501

23.30 7601

24.30 7701

25.30 7801

26.30 7901

27.30 8001

28.30 8101

29.30 8201

30.30 8301

31.30 8401

32.30 8501

33.30 8601

34.30 8701

35.30 8801

36.30 8901

37.30 9001

38.30 9101

39.30 9201

40.30 9301

41.30 9401

42.30 9501

43.30 9601

44.30 9701

45.30 9801

46.30 9901

47.30 10001

48.30 10101

49.30 10201

50.30 10301

51.30 10401

52.30 10501

53.30 10601

54.30 10701

55.30 10801

56.30 10901

57.30 11001

58.30 11101

59.30 11201

60.30 11301

61.30 11401

62.30 11501

PEAK FLOW AND STORAGE TEND-OF-PERIOD: SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND (CUBIC METERS PER SECOND)
 AREA IN SQUARE MILES (SQUARE KILOMETERS)

OPERATION	STATION	AREA	PLAN RATIO	RATIOS APPLIED TO FLOWS					
				RATIO 1	RATIO 2	RATIO 3	RATIO 4	RATIO 5	RATIO 6
				.10	.20	.30	.50	.80	1.00
HYDROGRAPH AT	1	.20 (.67)	1	77. (2.18)	154. (4.35)	231. (6.53)	384. (10.88)	615. (17.41)	769. (21.76)
	2	.26 (.67)	1	11. (.31)	14. (.40)	57. (1.62)	223. (6.30)	541. (15.32)	720. (20.38)
ROUTED TO	3	.21 (.54)	1	68. (1.92)	136. (3.85)	204. (5.77)	340. (9.62)	543. (15.39)	679. (19.23)
	4	.47 (1.22)	1	77. (2.17)	147. (4.17)	217. (6.13)	419. (11.86)	1005. (28.47)	1309. (37.08)
ROUTED TO	5	.47 (1.22)	1	13. (.55)	108. (3.06)	183. (5.16)	417. (11.80)	965. (27.34)	1326. (37.56)

SPAULDING POND DAM NO. 1

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1	INITIAL VALUE	SPILLWAY CREST	TOP OF DAM
	ELEVATION	241.00	250.50
	STORAGE	0.	151.
	OUTFLOW	0.	2105.

RATIO OF PMF	MAXIMUM RESERVOIR W.S.ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.10	242.63	0.00	22.	11.	0.00	44.50	0.00
.20	244.35	0.00	47.	14.	0.00	45.50	0.00
.30	245.59	0.00	66.	17.	0.00	44.00	0.00
.40	246.94	0.00	86.	23.	0.00	43.00	0.00
.50	247.55	0.00	98.	51.	0.00	42.00	0.00
1.00	247.89	0.00	104.	720.	0.00	41.50	0.00

13

SPAULDING POND DAM NO. 2

SUMMARY OF DAM SAFETY ANALYSIS

PLAN 1		INITIAL VALUE	SPILLWAY CREST	TOP OF DAM			
ELEVATION		159.00	159.00	172.30			
STORAGE		4.	4.	63.			
OUTFLOW		0.	0.	275R.			
RATIO OF PPE	MAXIMUM RESERVOIR W.S. ELEV	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE AC-FT	MAXIMUM OUTFLOW CFS	DURATION OVER TOP HOURS	TIME OF MAX OUTFLOW HOURS	TIME OF FAILURE HOURS
.10	165.37	0.00	20.	19.	0.00	44.50	0.00
.20	166.90	0.00	27.	108.	0.00	42.00	0.00
.30	167.68	0.00	31.	183.	0.00	41.50	0.00
.40	168.95	0.00	39.	417.	0.00	42.50	0.00
.50	169.49	0.00	45.	975.	0.00	42.00	0.00
1.00	170.67	0.00	50.	1370.	0.00	41.50	0.00

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING POND LAH #2

SHEET NO

OF

CALCULATED BY

K.A.

DATE

4/28/81

CHECKED BY


M.R.

DATE

5/7/81

SCALE

SCHEMATIC



- 1- SITE #1 INFLOW
- 2- SITE #1 ROUTED OUTFLOW
- 3- SITE #2 INFLOW
- 4- COMBINE HYDROGRAPHS 2 AND 3
- 5- SITE #2 ROUTED OUTFLOW

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING POND DAM #2
SHEET NO 2 OF _____
CALCULATED BY K.A. DATE 4/28/81
CHECKED BY M.R. DATE 5/7/81
SCALE _____

WATERSHED AREA - SPAULDING POND DAM #2

SITE NO. 1 (NORWICH, CONN. QUAD.)

106 grads } 106 grads \Rightarrow 155 Ac. 0.24 S.M.
106 " }

SITE NO. 2 (NORWICH, CONN. QUAD.)

107 grads } 106 grads \Rightarrow 155 Ac. (0.24 S.M.)
105 " }
106 " }

Use SC2 \Rightarrow 132 Ac. 0.21 S.M.

TOTAL WATERSHED 0.45 S.M.

WATERSHED AREA - SPAULDING POND DAM #1

FROM SC2 & ADKE I REPORT 0.26 S.M.

PRECIPITATION

U.S. WEATHER BUREAU
Tech. Paper No. 40

PREF. 6-1-10 25.2 INCHES

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPALLING Pond DAM #2

SHEET NO 3

CALCULATED BY K.A.

CHECKED BY M.R.

SCALE ---

OF

DATE

DATE

5/6/81

5/7/81

LAG TIME (SNYDER'S)

$$t_p = C_t (L L_{CA})^{0.3}$$

SPALLING Pond DAM #1:

$$C_t = 2.0$$

$$L = 4500' = 0.85 \text{ MI.}$$

$$L_{CA} = 1800' = 0.34 \text{ MI.}$$

$$t_p = 2.0 [(0.85)(0.34)]^{0.3}$$

$$t_p = 1.38 \text{ HRS.}$$

SPALLING Pond DAM #2:

$$C_t = 2.0$$

$$L = 2800' = 0.53 \text{ MI.}$$

$$L_{CA} = 1550' = 0.29 \text{ MI.}$$

$$t_p = 2.0 [(0.53)(0.29)]^{0.3}$$

$$t_p = 1.14 \text{ HRS.}$$

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING POND DAM #1

SHEET NO. 4

CALCULATED BY K.A.

CHECKED BY MR.

SCALE _____

OF


DATE

5/6/91

DATE

5/2/91

OUTFLOW RATING CURVE - SPAULDING POND DAM #1
FROM SCS & PHASE I REPORT (BY CAHN ENG.)



LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAILLING POND DAM #2

SHEET NO 5

CALCULATED BY K.A.

CHECKED BY MR

SCALE


OF

DATE 5/6/81

DATE 5/7/81

OUTFLOW RATING CURVE - SPAILLING POND DAM #2

ELEV. (FT.)	Q-PRINCIPAL SPILLWAY	Q-EMERGENCY SPILLWAY	Q-TOTAL (CFS)
159	0	0	0
160	5.7	0	5.7
162	12.7	0	12.7
164	17.0	0	17.0
166	20.4	0	20.4
168.7	79.1	203	282
170.7	85.1	1257	1344
171.7	88.0	2140	2228



LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING Pond Dam #2
SHEET NO. 6 OF _____
CALCULATED BY K.A. DATE 5/6/81
CHECKED BY M.R. DATE 5/7/81
SCALE _____


WATER SURFACE AREAS & STORAGE

SPAULDING Pond Dam #1: (FROM PHASE I REPORT)

NORMAL POOL ELEV. 241.0' 13 AC.
FLOOD POOL ELEV. 246.0' 10 AC.
(LINEAR VARIATION WITHIN
EXPECTED SURCHARGE)

SPAULDING Pond Dam #2: (FROM SCS - SEE APPENDIX B)

ELEV.	W. OF WOOD RD.	E. OF WOOD ROAD	TOTAL (AC. FT.)
160	3.75	0	3.75
162	7.91	0	7.91
164	12.58	2.00	14.58
166	17.78	4.92	22.70
168	24.02	8.68	32.70
170	31.81	13.56	45.37
172	41.56	18.92	60.48
174	54.22	25.36	79.58
176	70.43	32.90	103.33



LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING Pond DAM #2
SHEET NO DF-1 OF 15
CALCULATED BY K.A. DATE 4/23/81
CHECKED BY MR DATE 5/7/81
SCALE

DAM FAILURE ANALYSIS

DAM LENGTH = 200'

DAM LENGTH AT 110' HEIGHT = 120'

PEAK FAILURE OUTFLOW:

$$Q_{p1} = \frac{8}{27} \sqrt{16} \sqrt{g} y_o^{3/2}$$

$$W_b = 0.4 \times 120' = 48'$$

$$g = 32.2 \text{ FT/S}^2$$

$$y_o = 16.0'$$

$$Q_{p1} = \frac{8}{27} (48) (32.2^{1/2}) (16.0^{3/2})$$

$$\underline{Q_{p1} = 5165 \text{ CFS}}$$

STORAGE

AT TOP DAM
FROM 200

$$\underline{S = 54.2 \text{ AC.FT.}}$$


LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAWLING POND DAM #2
SHEET NO DF-2 OF 18
CALCULATED BY K.A. DATE 4/28/81
CHECKED BY M.R. DATE 5/17/81
SCALE HORIZ. 1"=100' VERT. 1"=4'

SECTION #1

STATION 3+00



<u>H</u>	<u>A</u>	<u>WP</u>	<u>R</u>	<u>n</u>	<u>✓</u>	<u>Q (cfs)</u>
2	60	61	1.0	.05	6.9	414
4	240	120	2.0	.05	10.9	2,616
6	535	170	3.1	.05	14.6	7,511
8	915	210	4.4	.05	18.4	16,836
10	1375	250	5.5	.05	21.4	29,425
12	1907	282	6.8	.05	24.7	47,102
14	2505	316	7.9	.05	27.2	68,136

L = 300 ft
g = .005 ft/ft

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING POND DAM #2

SHEET NO DF-3

OF 15

CALCULATED BY K.A.


DATE 4/28/81

CHECKED BY M.R.

DATE 5/7/81

SCALE

SECTION #1 (CONT.)



$$Q_{p1} = 5165 \text{ cfs}$$

$$H = 5.1 \text{ ft.}$$

$$A = 396 \text{ sq. ft.}$$

$$V_1 = 2.7 \text{ oc. ft.}$$

$$(\text{TRIAL}) Q_{p2} = 4908 \text{ cfs}$$

$$H = 5.0 \text{ ft.}$$

$$A = 315 \text{ sq. ft.}$$

$$V_2 = 2.6 \text{ oc. ft.}$$

$$Q_{p2} = 4912 \text{ cfs}$$

$$H = 5.0 \text{ ft.}$$


LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING Pond Dam #2
SHEET NO DF-4 OF 15
CALCULATED BY K.A. DATE 4/29/81
CHECKED BY M.R. DATE 5/17/81
SCALE HORIZ. 1"=100', VERT. 1"=4'

SECTION #2

STATION 10+00



<u>H</u>	<u>A</u>	<u>WP</u>	<u>R</u>	<u>n</u>	<u>V</u>	<u>Q (cfs)</u>
2	720	370	2.0	.06	5.1	3,672
4	1506	416	3.6	.06	7.6	11,445
6	2382	460	5.2	.06	9.7	23,105
8	3342	500	6.7	.06	11.5	33,433
3	1101	392	2.8	.06	6.4	7,046


$L = 100'$
 $S = .017$

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING ROAD DAM #2
SHEET NO DF-5 OF 16
CALCULATED BY K.A. DATE 4/29/81
CHECKED BY MR DATE 5/7/81
SCALE

SECTION #2 (CONT.)



$$Q_{P2} = 4912 \text{ cfs}$$

$$H = 2.4 \text{ ft.}$$

$$A = 885 \text{ sq. ft.}$$

$$V_1 = 14.2 \text{ ac. ft.}$$

$$(\text{TRIAL}) Q_{P3} = 3625 \text{ cfs}$$

$$H = 2.0 \text{ ft.}$$

$$A = 725 \text{ sq. ft.}$$

$$V_2 = 11.7 \text{ ac. ft.}$$

$$Q_{P3} = 3738 \text{ cfs}$$

$$H = 2.1 \text{ feet}$$


LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPaulding Pond Dam #2
SHEET NO DF-6 OF 18
CALCULATED BY K.A. DATE 4/29/81
CHECKED BY M.R. DATE 5/7/81
SCALE HOR. 1" = 100', VER. 1" = 4'

SECTION #3

STATION 25+00



<u>H</u>	<u>A</u>	<u>WP</u>	<u>R</u>	<u>n</u>	<u>V</u>	<u>Q (cfs)</u>
2	156	106	1.5	.04	3.3	515
4	422	160	2.6	.05	3.8	1604
6	798	216	3.7	.05	4.9	3910
8	1284	270	4.8	.05	5.3	7447


$L = 1500 \text{ ft.}$
 $S = .00467$

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPRAULDING POND DAM #2
SHEET NO DF-7 OF 18
CALCULATED BY K.A. DATE 4/22/81
CHECKED BY M.R. DATE 5/7/81
SCALE _____

SECTION #3 (CONT.)



$$Q_{P3} = 3728 \text{ cfs}$$

$$H = 5.8 \text{ ft.}$$

$$A = 760 \text{ sq. ft.}$$

$$V_1 = 26.2 \text{ ac. ft.}$$

$$(\text{TRIAL}) Q_{P4} = 1921 \text{ cfs}$$

$$H = 4.3 \text{ ft.}$$

$$A = 485 \text{ sq. ft.}$$

$$V_2 = 16.7 \text{ ac. ft.}$$

$$Q_{P4} = 2850 \text{ cfs}$$

$$H = 4.9 \text{ ft.}$$

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPaulding Pond Dam #2

SHEET NO. DF-2 OF 18


CALCULATED BY K.A. DATE 4/29/81

CHECKED BY M.R. DATE 5/7/81

SCALE HOR. 1"=100', VER. 1"=4'

SECTION #4

STATION 35+00



<u>H</u>	<u>A</u>	<u>WP</u>	<u>R</u>	<u>n</u>	<u>V</u>	<u>Q (cfs)</u>
2	140	140	1.0	.04	5.4	756
4	560	280	2.0	.05	6.8	3,308
6	1235	370	3.3	.05	9.6	11,856
8	2015	410	4.9	.05	12.4	24,256
3	315	210	1.5	.05	5.6	1,664

$L = 1000 \text{ ft.}$
 $S = 0.021 \text{ ft./ft.}$

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING POND LAKE #2

SHEET NO DF-9

OF 18

CALCULATED BY K.A.


DATE 4/27/81

CHECKED BY M.R.

DATE 5/7/81

SCALE

SECTION #4 (CONT.)



$$Q_{P4} = 2250 \text{ cfs}$$

$$H = 3.4 \text{ ft.}$$

$$A = 390 \text{ sq. ft.}$$

$$V_1 = 9.0 \text{ ac. ft.}$$

$$(\text{TRIAL}) Q_{P5} = 1884 \text{ cfs}$$

$$H = 3.1 \text{ ft.}$$

$$A = 338 \text{ sq. ft.}$$

$$V_2 = 7.8 \text{ ac. ft.}$$

$$Q_{P5} = 1910 \text{ cfs}$$

$$H = 3.2 \text{ ft.}$$

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING ROAD DAM #2

SHEET NO DF-10

CALCULATED BY K.A.

CHECKED BY MR

SCALE


OF 18

DATE 4/29/81

DATE 5/8/81

SECTION #5

STATION 45+00



<u>H</u>	<u>A</u>	<u>WP</u>	<u>R</u>	<u>n</u>	<u>V</u>	<u>Q(cfs)</u>
2	450	250	1.8	.05	10.8	4860
3	713	276	2.6	.05	13.6	9839
4	1001	300	3.3	.05	16.1	16,116
1	212	224	1.0	.05	7.3	1548
0.5	103	212	0.5	.05	4.6	474

$L = 1000 \text{ ft.}$
 $S = 0.06 \text{ ft./ft.}$

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING POND LAM #2

SHEET NO DF-11

OF 15

CALCULATED BY K.A.


DATE 4/29/81

CHECKED BY MR

DATE 5/8/81

SCALE

SECTION # I (CONT.)



$$Q_{p5} = 1910 \text{ cfs}$$

$$H = 1.1 \text{ ft.}$$

$$A = 245 \text{ sq. ft.}$$

$$V_1 = 5.6 \text{ ac. ft.}$$

$$(\text{TRIAL}) Q_{p6} = 1713 \text{ cfs}$$

$$H = 1.1 \text{ ft.}$$

$$A = 230 \text{ sq. ft.}$$

$$V_2 = 5.3 \text{ ac. ft.}$$

$$Q_{p6} = 1718 \text{ cfs}$$

$$H = 1.1 \text{ ft.}$$

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING POND DAM #2
SHEET NO DF-12 OF 15
CALCULATED BY K.A. DATE 5/12/81
CHECKED BY DATE 5/12/81
SCALE

DIKE FAILURE ANALYSIS

$$\text{DIKE LENGTH} = 900'$$

PEAK FAILURE OUTFLOW:

$$Q_{PI} = \frac{8}{27} W_b \sqrt{g} Y_0^{3/2}$$

$$W_b = 100'$$

$$g = 32.2 \text{ FT/}^2$$

$$Y_0 = 15'$$

$$Q_{PI} = \frac{8}{27} (100) (32.2^{1/2}) (15^{3/2})$$

$$\underline{Q_{PI} = 9770 \text{ CFS}}$$

STORAGE

$$\underline{S = 20 \text{ AC. FT.}}$$

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING POND DAM #2

SHEET NO DF-13

OF 18

CALCULATED BY K.A.

DATE 5/12/81


CHECKED BY

DATE 5/12/81

SCALE HORIZ. 1"=100' VERT. 1"=4'

SECTION #1

STATION 6+00



H	A	WP	R	n	V	Q (cfs)
2	550	300	1.8	.06	6.6	3630
4	1186	336	3.5	.06	10.2	12,097
6	1692	370	5.1	.06	13.1	24,735
8	2270	408	6.5	.06	15.4	41,113
3	369	216	2.7	.06	8.6	7337

400 ft.
100 ft. / ft.

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB *SPOULDING Pond Dam #2*

SHEET NO *DF-14*

OF *18*

CALCULATED BY *K.A.*


DATE *5/12/81*

CHECKED BY *M.E.*

DATE *5/12/81*

SCALE

SECTION #1 (CONT.)



$$Q_{p1} = 9770 \text{ cfs}$$

$$H = 3.5 \text{ ft.}$$

$$A = 1030 \text{ sq. ft.}$$

$$V_1 = 14.2 \text{ ac. ft.}$$

$$(\text{TRIAL}) Q_{p2} = 2840 \text{ cfs}$$

$$H = 1.8 \text{ ft.}$$

$$A = 480 \text{ sq. ft.}$$

$$V_2 = 6.6 \text{ ac. ft.}$$

$$Q_{p2} = 4690 \text{ cfs}$$

$$H = 2.3 \text{ ft.}$$

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING POND DAM #2
SHEET NO. DF-15 OF 18
CALCULATED BY K.A. DATE 5/12/81
CHECKED BY M.K. DATE 5/13/81
SCALE HORIZ. 1" = 100', VERT. 1" = 4'

SECTION #2

STATION 9+00



<u>H</u>	<u>A</u>	<u>WP</u>	<u>R</u>	<u>n</u>	<u>V</u>	<u>Q (cfs)</u>
1	455	460	1.0	.05	2.4	1,092
2	914	464	2.0	.05	3.9	3,565
3	1359	486	2.9	.05	4.9	6,806
4	1882	500	3.8	.05	5.9	11,104


$L = 500 \text{ ft.}$
 $c = .0067 \text{ ft./ft.}$

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPAULDING POND DAM #2
SHEET NO. DF-16 OF 18
CALCULATED BY K. A. DATE 5/12/81
CHECKED BY M. R. DATE 5/13/81
SCALE

SECTION #2 (CONT.)



$$Q_{p2} = 4690 \text{ cfs}$$

$$H = 2.4 \text{ ft.}$$

$$A = 1100 \text{ sq. ft.}$$

$$V_1 = 7.6 \text{ ac. ft.}$$

$$(\text{TRIAL}) Q_{p3} = 2908 \text{ cfs}$$

$$H = 1.8 \text{ ft.}$$

$$A = 815 \text{ sq. ft.}$$

$$V_2 = 5.6 \text{ ac. ft.}$$

$$Q_{p3} = 3142 \text{ cfs}$$

$$H = 1.9 \text{ ft.}$$


LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB: SPAULDING POND DAM #2
SHEET NO. DF-17 OF 18
CALCULATED BY K.A. DATE 5/12/81
CHECKED BY 1/2/81 DATE 5/12/81
SCALE HORIZ. 1" = 100' VERT. 1" = 4'

SECTION #3

STATION 12+00



<u>H</u>	<u>A</u>	<u>W/D</u>	<u>R</u>	<u>11</u>	<u>V</u>	<u>Q(cfs)</u>
1	554	558	1.0	.05	2.4	1330
2	1116	566	2.0	.05	3.9	4352
3	1686	574	2.9	.05	4.9	8261
4	2264	582	3.9	.05	6.0	13584
15	840	562	1.5	.05	3.2	2688


$L = 300 \text{ ft.}$
 $S = .0067 \text{ ft./ft.}$

LENARD & DILAJ ENGINEERING, INC.

1066 Storrs Road
STORRS, CONNECTICUT 06268
(203) 429-7308

JOB SPaulding Pond LAM #2
SHEET NO DF-18 OF 18
CALCULATED BY K.A. DATE 5/12/91
CHECKED BY 11/1 DATE 5/12/91
SCALE _____

SECTION #2 (CONT.)



$$Q_{P3} = 3142 \text{ cfs}$$

$$H = 1.7 \text{ ft.}$$

$$A = 930 \text{ sq. ft.}$$

$$V_1 = 6.4 \text{ ac. ft.}$$

$$(TRIAL) Q_{P4} = 2136 \text{ cfs}$$


$$H = 1.3 \text{ ft.}$$

$$A = 740 \text{ sq. ft.}$$

$$V_2 = 5.1 \text{ ac. ft.}$$

$$Q_{P4} = 2240 \text{ cfs}$$

$$H = 1.3 \text{ ft.}$$



APPENDIX E

INFORMATION AS CONTAINED IN THE
NATIONAL INVENTORY OF DAMS

品

INVENTION OF DAMS IN THE UNITED STATES PURSUANT TO PUBLIC LAW 92-367)

See reverse side for: 7-1-05

U.S. GOVERNMENT PRINTING OFFICE

PART I - INVENTORY OF DAMS IN THE UNITED STATES
(PURSUANT TO PUBLIC LAW 92-367)

See reverse side for 1973 figures

STATE	IDENTITY NUMBER
1	1 4 3 6 7
2	0 1 7 1 2
CT	

	[2]	[3]	[4]	[5]	[6]	[7]	[8]	[9]	[10]	[11]	[12]
IDENTIFICATION	DIVISION	STATE	COUNTY	CONGR DIST	STATE	COUNTY	CONGR DIST	NAME	LATITUDE (N or S)	LONGITUDE (W or E)	REPORT DATE
											DAY MO YR
N 00	CT 01102							S HADWIN CT BPOOK ST NO 2 - DIKE #12 + 972341	/ /	/ /	02 SEP 81

[illegible]

[15] [16]		[17]	[18]	[19]	[20]
LOCATION	REGION	RIVER OR STREAM	NEAREST DOWNSTREAM CITY - TOWN - VILLAGE	FORM DAM (YES)	POPULATION
01105	REDUING	PODIBROČ	NORVICH	1	43402

[21]		[22]	[23]	[24]	[25]	[26]		[27]	[28]	[29]	[30]	[31]
TYPE OF DAM		YEAR COMPLETED	PURPOSES	STRUCTURAL HEIGHT (FT)	HYDRAULIC HEIGHT (FT)	IMPOUNDING CAPACITIES			CORPUS ENGR DIST	VERIFICATION DATE	BLANK	
						MAX VOLUME	NO. VAL					
89	10	1968	24	18	15	63						
REPC		1968	CP	18	15	63						

REMARKS		REMARKS	
8	9	10	11
12	13	14	15
16	17	18	19
20	21	22	23
24	25	26	27
28	29	30	31
32	33	34	35
36	37	38	39
40	41	42	43
44	45	46	47
48	49	50	51
52	53	54	55
56	57	58	59
60	61	62	63
64	65	66	67
68	69	70	71
72	73	74	75
76	77	78	79
80	81	82	83
84	85	86	87
88	89	90	91
92	93	94	95
96	97	98	99
100	101	102	103
104	105	106	107
108	109	110	111
112	113	114	115
116	117	118	119
120	121	122	123
124	125	126	127
128	129	130	131
132	133	134	135
136	137	138	139
140	141	142	143
144	145	146	147
148	149	150	151
152	153	154	155
156	157	158	159
160	161	162	163
164	165	166	167
168	169	170	171
172	173	174	175
176	177	178	179
180	181	182	183
184	185	186	187
188	189	190	191
192	193	194	195
196	197	198	199
200	201	202	203
204	205	206	207
208	209	210	211
212	213	214	215
216	217	218	219
220	221	222	223
224	225	226	227
228	229	230	231
232	233	234	235
236	237	238	239
240	241	242	243
244	245	246	247
248	249	250	251
252	253	254	255
256	257	258	259
260	261	262	263
264	265	266	267
268	269	270	271
272	273	274	275
276	277	278	279
280	281	282	283
284	285	286	287
288	289	290	291
292	293	294	295
296	297	298	299
300	301	302	303
304	305	306	307
308	309	310	311
312	313	314	315
316	317	318	319
320	321	322	323
324	325	326	327
328	329	330	331
332	333	334	335
336	337	338	339
340	341	342	343
344	345	346	347
348	349	350	351
352	353	354	355
356	357	358	359
360	361	362	363
364	365	366	367
368	369	370	371
372	373	374	375
376	377	378	379
380	381	382	383
384	385	386	387
388	389	390	391
392	3		

PART II - INVENTORY OF DAMS IN THE UNITED STATES
(PURSUANT TO PUBLIC LAW 92-367)

See revision 3 for instructions

FORM APPROVED
OMB NO. 49-00421

REQUIREMENTS CONTROL SYMBOL
DAEN-CWE-17

IDENTITY NUMBER
STATE

[29]	[30]	[31]	[32]	[33]	[34]	[35]	[36]	[37]	[38]	[39]	[40]	[41]	[42]	[43]	[44]	[45]
STATISTICS				SPILLWAY		POWER CAPACITY		NAVIGATION LOCKS								
CREST LENGTH (ft)	WIDTH (ft)	MAXIMUM DISCHARGE (cfs)	VOLUME OF DAM (cu ft)	INSTALLED (MW)	PRODUCED (MW)	LENGTH (ft)	WIDTH (ft)	LENGTH (ft)	WIDTH (ft)	LENGTH (ft)	WIDTH (ft)	LENGTH (ft)	WIDTH (ft)	LENGTH (ft)	WIDTH (ft)	BLANK
1	9.00		11000		0											5

[46]	[47]	[48]
MISC DATA	ENGINEERING BY	CONSTRUCTION BY
1		

[49]	[50]	[51]	[52]
MISC DATA (Continued)	REGULATORY AGENCY	OPERATION	MAINTENANCE
1			

[53]	[54]	[55]
MISC DATA (Continued)	INSPECTION BY	AUTHORITY FOR INSPECTION
1		

[56]
REMARKS
1

①

PART III - INVENTORY OF DAMS IN THE UNITED STATES SUPPLEMENTARY DATA		STATE	IDENTITY NUMBER
		CT	1712

(A-1) (A-2) (A-3) (A-4) (A-5)

LOCATION	TOWN	NED PERMIT NO	STATE NUMBER	FERC NO	USGS SHEET
NEW RICH					

(B-1) (B-2) (B-3) (B-4) (B-5) (B-6) (B-7) (B-8) (B-9) (B-10) (B-11) (B-12)

DRAINAGE CHARACTERISTICS	DRAINAGE AREA SQ MI	FLOW DATA			CREST ELEV MSL	ABUT ELEV MSL	USABLE STORAGE ACRES	RESERVOIR AREA ACRES	FLASH BOARD HT FEET	OUTLET CONDUITS NO	INVERT ELEV MSL
		MIN CFS	AVE CFS	MAY CFS							
	1				172		60	3		0	

(C-1) (C-2) (C-3) (C-4) (C-5) (C-6) (C-7)

POWER DATA	GENERATION UNITS			AVERAGE ANNUAL GENERATION KWH	LAST GEN YEAR	RETIRED YEAR	FORMER USE	CAPACITY FACTOR
	INSTALLED NO CAP KWH	NO CAP KWH	PLANNED KWH					

B-2 NO SPILLWAY OR OUTLET ON Dike F 8 BORMAT									
----------------------------------------------	--	--	--	--	--	--	--	--	--

--	--	--	--	--	--	--	--	--	--

NED FORM 1 JAN 79 80 (TEST)

11

WASH DC

PART I - INVENTORY OF DAMS IN THE UNITED STATES
(PURSUANT TO PUBLIC LAW 92-367)

See reverse side for instructions

STATE	IDENTITY NUMBER	II
CA	00217B	


[illegible]

IDENTIFICATION (Continued)	POPULAR NAME	NAME OF IMPOUNDMENT
8	1	1
9	2	2
10	3	3
11	4	4
12	5	5
13	6	6
14	7	7
15	8	8
16	9	9
17	10	10
18	11	11
19	12	12
20	13	13
21	14	14
22	15	15
23	16	16
24	17	17
25	18	18
26	19	19
27	20	20
28	21	21
29	22	22
30	23	23
31	24	24
32	25	25
33	26	26
34	27	27
35	28	28
36	29	29
37	30	30
38	31	31
39	32	32
40	33	33
41	34	34
42	35	35
43	36	36
44	37	37
45	38	38
46	39	39
47	40	40
48	41	41
49	42	42
50	43	43
51	44	44
52	45	45
53	46	46
54	47	47
55	48	48
56	49	49
57	50	50
58	51	51
59	52	52
60	53	53
61	54	54
62	55	55
63	56	56
64	57	57
65	58	58
66	59	59
67	60	60
68	61	61
69	62	62
70	63	63
71	64	64
72	65	65
73	66	66
74	67	67
75	68	68
76	69	69
77	70	70
78	71	71
79	72	72
80	73	73
81	74	74
82	75	75
83	76	76
84	77	77
85	78	78
86	79	79
87	80	80
88	81	81
89	82	82
90	83	83
91	84	84
92	85	85
93	86	86
94	87	87
95	88	88
96	89	89
97	90	90
98	91	91
99	92	92
100	93	93
101	94	94
102	95	95
103	96	96
104	97	97
105	98	98
106	99	99
107	100	100
108	101	101
109	102	102
110	103	103
111	104	104
112	105	105
113	106	106
114	107	107
115	108	108
116	109	109
117	110	110
118	111	111
119	112	112
120	113	113
121	114	114
122	115	115
123	116	116
124	117	117
125	118	118
126	119	119
127	120	120
128	121	121
129	122	122
130	123	123
131	124	124
132	125	125
133	126	126
134	127	127
135	128	128

LOCATION	REGION	BASIN	RIVER OR STREAM	NEAREST DOWNSTREAM CITY - TOWN - VILLAGE	DIST FROM DATA	POPULATION
01108-1A-LALING POND BROOK				NORRICH	1	434092

STATISTICS	TYPE OF DAM	YEAR COMPLETED	PURPOSES	STRUCTURAL HEIGHT (ft)	HYDRAULIC HEAD (ft)	IMPOUNDING CAPACITIES		CHINA'S OWNERS	VERIFICATION DATE	BLANK
						MAXIMUM	NORMAL			
1	1	1954	1	1	1	1	1	1	1	1
2	2	1955	2	2	2	2	2	2	2	2
3	3	1956	3	3	3	3	3	3	3	3
4	4	1957	4	4	4	4	4	4	4	4
5	5	1958	5	5	5	5	5	5	5	5
6	6	1959	6	6	6	6	6	6	6	6
7	7	1960	7	7	7	7	7	7	7	7
8	8	1961	8	8	8	8	8	8	8	8
9	9	1962	9	9	9	9	9	9	9	9
10	10	1963	10	10	10	10	10	10	10	10
11	11	1964	11	11	11	11	11	11	11	11
12	12	1965	12	12	12	12	12	12	12	12
13	13	1966	13	13	13	13	13	13	13	13
14	14	1967	14	14	14	14	14	14	14	14
15	15	1968	15	15	15	15	15	15	15	15
16	16	1969	16	16	16	16	16	16	16	16
17	17	1970	17	17	17	17	17	17	17	17
18	18	1971	18	18	18	18	18	18	18	18
19	19	1972	19	19	19	19	19	19	19	19
20	20	1973	20	20	20	20	20	20	20	20
21	21	1974	21	21	21	21	21	21	21	21
22	22	1975	22	22	22	22	22	22	22	22
23	23	1976	23	23	23	23	23	23	23	23
24	24	1977	24	24	24	24	24	24	24	24
25	25	1978	25	25	25	25	25	25	25	25
26	26	1979	26	26	26	26	26	26	26	26
27	27	1980	27	27	27	27	27	27	27	27
28	28	1981	28	28	28	28	28	28	28	28
29	29	1982	29	29	29	29	29	29	29	29
30	30	1983	30	30	30	30	30	30	30	30
31	31	1984	31	31	31	31	31	31	31	31
32	32	1985	32	32	32	32	32	32	32	32
33	33	1986	33	33	33	33	33	33	33	33
34	34	1987	34	34	34	34	34	34	34	34
35	35	1988	35	35	35	35	35	35	35	35
36	36	1989	36	36	36	36	36	36	36	36
37	37	1990	37	37	37	37	37	37	37	37
38	38	1991	38	38	38	38	38	38	38	38
39	39	1992	39	39	39	39	39	39	39	39
40	40	1993	40	40	40	40	40	40	40	40
41	41	1994	41	41	41	41	41	41	41	41
42	42	1995	42							

[illegible]

<div>  PART II - INVENTORY OF DAMS IN THE UNITED STATES (PURSUANT TO PUBLIC LAW 92-367) </div>										FORM APPROVED OMB NO. 49-R121 REQUIREMENTS CONTROL SYMBOL DAER-CWE-17		IDENTITY NUMBER 1 2 3 4 5 6 7 C 0 0 2 0 3	
See reverse side for instructions													

[29]		[30]	[31]	[32]	[33]	[34]	[35]	[36]	[37]	[38]	[39]	[40]	[41]	[42]	[43]	[44]	[45]								
STATISTICS		CREST LENGTH (ft)		SPILLWAY		VOLUME OF DAM (CY)		POWER CAPACITY		NAVIGATION LOCKS								BLANK							
		TYPE		WIDTH (ft)		MAXIMUM DISCHARGE (ft)		INSTALLED (MW)		PRODUCED (MW)		LENGTH (ft)		WIDTH (ft)		LENGTH (ft)		WIDTH (ft)		LENGTH (ft)		WIDTH (ft)		BLANK	
1		200		115		2850		7500		7500		7500		7500		7500		7500		7500		7500		7500	

[46]										[47]										[48]																			
MISC DATA										OWNER										ENGINEERING BY										CONSTRUCTION BY									
1										2										3										4									
5										6										7										8									
9										10										11										12									
13										14										15										16									
17										18										19										20									
21										22										23										24									
25										26										27										28									
29										30										31										32									
33										34										35										36									
37										38										39										40									
41										42										43										44									
45										46										47										48									
49										50										51										52									
53										54										55										56									
57										58										59										60									
61										62										63										64									
65										66										67										68									
69										70										71										72									
73										74										75										76									
77										78										79										80									
81										82										83										84									
85										86										87										88									
89										90										91										92									
93										94										95										96									
97										98										99										100									

[49]										[50]										[51]										[52]																			
MISC DATA										DESIGN										CONSTRUCTION										OPERATION										MAINTENANCE									
1										2										3										4										5									
6										7										8										9										10									
11										12										13										14										15									
16										17										18										19										20									
21										22										23										24										25									
26										27										28										29										30									
31										32										33										34										35									
36										37										38										39										40									
41										42										43										44										45									
46										47										48										49										50									
51										52										53										54										55									
56										57										58										59										60									
61										62										63										64										65									
66										67										68										69										70									
71										72										73										74										75									
76										77										78										79										80									
81										82										83										84										85									
86										87										88										89										90									
91										92										93										94										95									
96										97										98										99										100									

[53]										[54]										[55]																			
MISC DATA										INSPECTION BY										INSPECTION DATE										AUTHORITY FOR INSPECTION									
1										2										3										4									
5										6										7										8									
9										10										11										12									
13										14										15										16									
17										18										19										20									
21										22										23										24									
25										26										27										28									
29										30										31										32									
33										34										35										36									
37										38										39										40									
41										42										43										44									
45										46										47										48									
49										50										51										52									
53										54										55										56									
57										58										59										60									
61										62										63										64									
65										66										67										68									
69										70										71										72									
73										74										75										76									
77										78										79										80									
81										82										83										84									
85										86										87										88									
89										90										91										92									
93										94										95										96									
97										98										99										100									

[56]									
REMARKS									
1									
2									
3									
4									
5									
6									
7									
8									
9									
10									
11									
12									
13									
14									
15									
16									
17									
18									
19									
20									
21									
22									
23									
24									
25									
26									
27									
28									
29									
30									
31									
32									
33									
34									
35									
36									
37									
38									
39									
40									
41									
42									
43									
44									
45									
46									
47									
48									
49									
50									
51									
52									
53									
54									
55									
56									
57									
58									
59									
60									
61									
62									
63									
64									
65									
66									
67									
68									
69									
70									
71									
72									
73									
74									
75									
76									
77									
78									
79									
80									
81									
82									
83									
84									
85									
86									
87									
88									
89									
90									
91									
92									
93									
94									
95									
96									
97									
98									
99									
100									

PART III - INVENTORY OF DAMS IN THE UNITED STATES
SUPPLEMENTARY DATA

LOCATION	TOWN	MFD PERMIT NO	STATE NUMBER	FERC NO	USGS SHEET
NO. 1					
NO. 2					
NO. 3					
NO. 4					
NO. 5					
NO. 6					
NO. 7					
NO. 8					
NO. 9					
NO. 10					
NO. 11					
NO. 12					
NO. 13					
NO. 14					
NO. 15					
NO. 16					
NO. 17					
NO. 18					
NO. 19					
NO. 20					
NO. 21					
NO. 22					
NO. 23					
NO. 24					
NO. 25					
NO. 26					
NO. 27					
NO. 28					
NO. 29					
NO. 30					
NO. 31					
NO. 32					
NO. 33					
NO. 34					
NO. 35					
NO. 36					
NO. 37					
NO. 38					
NO. 39					
NO. 40					
NO. 41					
NO. 42					
NO. 43					
NO. 44					
NO. 45					
NO. 46					
NO. 47					
NO. 48					
NO. 49					
NO. 50					
NO. 51					
NO. 52					
NO. 53					
NO. 54					
NO. 55					
NO. 56					
NO. 57					
NO. 58					
NO. 59					
NO. 60					
NO. 61					
NO. 62					
NO. 63					
NO. 64					
NO. 65					
NO. 66					
NO. 67					
NO. 68					
NO. 69					
NO. 70					
NO. 71					
NO. 72					
NO. 73					
NO. 74					
NO. 75					
NO. 76					
NO. 77					
NO. 78					
NO. 79					
NO. 80					
NO. 81					
NO. 82					
NO. 83					
NO. 84					
NO. 85					
NO. 86					
NO. 87					
NO. 88					
NO. 89					
NO. 90					
NO. 91					
NO. 92					
NO. 93					
NO. 94					
NO. 95					
NO. 96					
NO. 97					
NO. 98					
NO. 99					
NO. 100					

DRAINAGE CHARACTERISTICS	DRAINAGE AREA SQ. MI.	FLOW DATA			CREST ELEV. MSL	ABUT. AREA MSL	USABLE STORAGE ACRES	RESERVOIR AREA ACRES	FLASH FLOODING FEET	OUTLET CONDITIONS	INVERT ELEV. MSL
		MIN. CFS	AVERAGE CFS	MAX. CFS							
1	1.1	1	1	1	172		60	3	0	1	172
2	1.1	1	1	1	172		60	3	0	1	172

[illegible]

	STANDARD PNEUMATIC CUSHION SEAMER	D
--	-----------------------------------	---

[illegible]

AD-A143 496

NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS
SPAULDING POND BROOK. (U) CORPS OF ENGINEERS WALTHAM MA
NEW ENGLAND DIV JUN 81

272

UNCLASSIFIED


F/G 13/13

NL

END


FILED

DTIC




MICROCOPY RESOLUTION TEST CHART
NATIONAL BUREAU OF STANDARDS-1963-A

- DRAIN INVERT OF PIPE
 ORIFICE INVERT = 155.0
 CREST FL = 168.1



①

10-1-68
 10-1-68
 10-1-68
 10-1-68




DROP INLET STRUCTURE
ORIFICE INVERT EL.=159.0
CREST EL.=166.3

TOP OF DAM EL.=172.3






TOP OF DIKE EL.=172.3

POND

SILTATION IN ARCH PIPE
CULVERT BENEATH ROAD




LEGEND



-  RIP RAP
-  EDGE OF ROAD
-  EDGE OF DIKE
-  EDGE OF POND
-  *4 TOE DRAIN

100 200
FEET

(2)


(3)





SCS-313B (APR. L 1963)

CN - 425 - P



①


Copy available to DTIC does not
permit fully legible reproduction

②


4. SPILLWAY DATA

STA	DEF. A	CHD
1+00	81.10	81.10
1+25	81.10	81.10
1+50	81.10	81.10
1+75	81.10	81.10
2+00	81.10	81.10

OUTLET CHAN
 4" DIA. RIGID
 DEF. & PER FT OF C



- LEGEND
- BRIDGE
 - CRILL HOLE
 - SURVEY TRAVERSE STATION
 - UTILITY POLE
 - APPROX. LIMIT OF ROCK OUTCROP
 - CONTOUR
 - LINE OF BRIDGE
 - FENCE
 - CLEARING & GRUBBING UNIT
 - WORK LIMITS



SPAUDING POND BRIDGE
 SPILLWAY FOR
 NORWICH CO
 PLAN OF STRUCTURE
 U.S. DEPARTMENT
 SOIL CONSERVATION


2

3

EMERGENCY SPILLWAY CURVE DATA


STA	DEF. A	CHD	
1+85			R = 12.81
1+50	4' 5" - 13'	34.38	T = 52.06
1+25	4' 12" - 33'	24.46	A = 51' - 42"
1+00	11' 58" - 33'		E = 13.55
0+75	23' 51" - 30'		M = 12.20


OUTLET CHANNEL
 A = 61' 00" B = 68.8' C = 70.8
 DEF. 4 PER FT OF CURVE = 0.4387'




SPAULDING POND BROOK WATERSHED PROJECT
 SPAULDING POND SITE NO 2
 NORWICH, CONNECTICUT
 PLAN OF STRUCTURAL WORKS
 U. S. DEPARTMENT OF AGRICULTURE
 SOIL CONSERVATION SERVICE

Designed by	Date	Approved by
Drawn by	12-50	Time
Traced	12-50	Time
Checked	12-50	Time
		File
		Sheet
		No. 5
		-19
		CN - 425 - P





CITY OF NORWICH



NOTES - SITE PLAN DISPOSITION LINE


1. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE TERMS OF THE CONTRACT AND THE TERMS OF THE AGREEMENT BETWEEN THE CITY OF NORWICH AND THE CONTRACTOR.
2. THE CONTRACTOR SHALL GIVE THE CITY OF NORWICH SUFFICIENT NOTICE IN WRITING TO ALLOW TIME FOR A COMPANY REPRESENTATIVE TO BE ON THE SITE AND SHALL NOT PROCEED WITH THE WORK WITHOUT PERMISSION FROM THE CITY.
3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL UTILITIES AND STRUCTURES ON THE SITE.

NO.	DATE	REVISION
1	10/1/73	1
2	10/1/73	2
3	10/1/73	3
4	10/1/73	4
5	10/1/73	5
6	10/1/73	6
7	10/1/73	7
8	10/1/73	8
9	10/1/73	9
10	10/1/73	10

Legend

- CONTOUR
- EDGE OF WOODS
- NATURAL GAS LINE
- WATER MAIN
- SEWER MAIN
- APPROX. LINE OF ROAD, BUT NOT
- APPROX. AREA OF INTEREST, BUT NOT THE EXACT BOUNDARY
- FENCE
- IRON PIPE
- WATER MAIN
- SEWER MAIN
- TRAVEL TRAIL
- TRAILING LINE
- WORKER LIMIT


SCALE 1" = 100' (SEE NOTE 1)



AS-BUILT

SPAUDS POND BR
PLAN OF SITE
U.S. DEPARTMENT OF
SOIL CONSERVATION

6



CURVE DATA

& DIKE

STA	DELT	CHD
2+00		4994
2+50	5° 02' 24"	
3+00	10° 03' 48"	
3+50	5° 07' 12"	
4+00	20° 09' 36"	
4+50	25° 12' 00"	39 92
4+99.39	29° 10' 00"	
Δ = 56° 20' R = 284.20' T = 158.62'		
L = 41.27' M = 86.03'		

& Connecting Culvert Ditch

SECTION T-400 R-600 E-780'

TERMINATION LINE

1. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE SPECIFICATIONS AND STANDARDS OF THE U.S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE, AND THE STATE OF CONNECTICUT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE APPROPRIATE AGENCIES. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES AT ALL TIMES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES AND STRUCTURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL DEBRIS AND WASTE MATERIAL FROM THE SITE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR OF ALL DAMAGE TO ADJACENT PROPERTIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL ADJACENT PROPERTIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL ADJACENT PROPERTIES.

DISPOSAL NOTES

1. ALL EXCAVATED MATERIAL SHALL BE DISPOSED OF IN ACCORDANCE WITH THE REQUIREMENTS OF THE STATE OF CONNECTICUT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND APPROVALS FROM THE APPROPRIATE AGENCIES. THE CONTRACTOR SHALL MAINTAIN ACCESS TO ALL ADJACENT PROPERTIES AT ALL TIMES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL EXISTING UTILITIES AND STRUCTURES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF ALL DEBRIS AND WASTE MATERIAL FROM THE SITE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REPAIR OF ALL DAMAGE TO ADJACENT PROPERTIES. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PROTECTION OF ALL ADJACENT PROPERTIES.
2. THE AREA SHALL BE GRADED TO DRAIN AS DIRECTED BY THE ENGINEER.

AS-BUILT

SPAULDING POND BROOK WATERSHED PROJECT SPAULDING POND SITE NO. 2 NORWICH, CONNECTICUT PLAN OF STRUCTURAL WORKS U. S. DEPARTMENT OF AGRICULTURE SOIL CONSERVATION SERVICE

Designed by H. L. L. & W. L. L.	Date 1965	Reviewed by J. L. L.
Drawn by J. L. L.	Checked by J. L. L.	Approved by J. L. L.
Scale 1" = 40'	Sheet No. 4	Project No. CN-425-P

565-1118 (APRIL 1963)





DRAIN PIPE NOTES

1. DRAIN PIPE SHALL BE 8" DIA. MATERIAL SPECIFIED AND SHOWN
 IN 5110 AND 5111. DRAIN PIPE SHALL BE 10' LONG.


II

A

OUTLET NO. 1




SECTION A-A



Size	Quantity
8"	100 Yds
6"	75-100
4"	60-80
3"	45-70
2"	25-50
1 1/2"	15-30
1"	10-20
3/4"	5-10
1/2"	5-10
3/8"	5-10
1/4"	5-10


3/8" Dia Bolts
 with Nut And Washers
 Spacing 4'




8" Dia Pipe

SMALL ANIMAL GUARD DETAILS

MINERAL SPILLWAY



ON D.O.



TYPICAL SECTION-DAM

NOT TO SCALE

THE DAM AND DAM EMBANKMENTS SHALL CONSIST OF EARTH FILL CLASS A COMPACTION CONSISTING MAINLY OF BEST SANDS (SANDS AND SILTS) AND FINE GRAINS. SILTS AND FINE GRAINS SHALL BE REPRESENTED BY THE FOLLOWING LOGS:

ON 54	FROM 17 TO 33	(SANDS AND SILTS)
ON 55	6.5	6.5 (SANDS AND SILTS)
ON 56	6.8	6.8 (SANDS AND SILTS)
ON 57	5.0	17.5 (SANDS AND SILTS)
ON 58	0.5	16.7 (SANDS AND SILTS)
ON 59	1.5	6.5 (SANDS AND SILTS)
ON 60	1.5	6.7 (SANDS AND SILTS)


COARSE MATERIALS CONSISTING MAINLY OF POBBLY GRADED SANDS (SANDS AND SILTS) SHALL BE REPRESENTED BY THE FOLLOWING LOGS: SANDS AND SILTS SHALL BE PLACED IN THE OUTER PORTION OF THE FILL AS DIRECTED BY THE ENGINEER.

ON 61 FROM 10 TO 15.5 (SANDS AND SILTS)

DETAILS OF DAM


ON 54

ON 54	FROM 17 TO 33	(SANDS AND SILTS)
ON 55	6.5	6.5 (SANDS AND SILTS)
ON 56	6.8	6.8 (SANDS AND SILTS)
ON 57	5.0	17.5 (SANDS AND SILTS)
ON 58	0.5	16.7 (SANDS AND SILTS)
ON 59	1.5	6.5 (SANDS AND SILTS)
ON 60	1.5	6.7 (SANDS AND SILTS)



3/8" Dia. Bolts
w/ Hex Nut And Washers
9" Long

Drill 1/2" Dia.
Holes



8" Dia. Pipe

SPAULDING POND BROOK WATERSHED PROJECT
SPAULDING POND SITE NO. 2
NORWICH, CONNECTICUT
DRAINAGE DETAILS - DAM
U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed by	Date	Approved by
Drawn by		
Checked by		
Project No.	Sheet No.	Scale


SMALL ANIMAL GUARD DETAILS

CN-425-P


3


Form 517, 11-77

THE ENGINEER WILL DETERMINE THE FINAL DEPTH OF
BEAM ELEVATION
THE ORG. GRADING AT ENDS OF OUTLETS SHALL BE
TO PROVIDE SUITABLE DRAINAGE AWAY FROM THE J
AS DIRECTED BY THE ENGR
FOR DESCRIPTION OF ORG. WELLS AND TEST PITS
TO SHEET 17, 18 & 19
REFER TO SHEET 18 FOR ORGAN PIPE NOTES AND
DRAIN FILL MATERIAL. GRADATION LIMITED



PROFILE ALONG & OF OUTLET NO. 4







TYPICAL SECTION - DIKE

NOT TO SCALE

REFER TO SHEET NO. 1 FOR FILL MATERIALS & COMPACTION NOTE



SPAULDING POND BROOK WATERSHED PROJECT


SPAULDING POND SITE NO 2
NORWICH, CONNECTICUT

DRAINAGE DETAILS - DIKE

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Drawn by W. H. Loomis, Jr.	Date 12-1-55	Approved by T. H.
Checked T. H.	Date 12-1-55	Approved by T. H.
Sheet 1 of 1	Drawn by W. H. Loomis, Jr.	Checked T. H.
CN - 425 - P		

ITEM	AMT	UNIT	QTY	PRICE	TOTAL
1	1.00	CU YD	1.00	1.00	1.00
2	1.00	CU YD	1.00	1.00	1.00
3	1.00	CU YD	1.00	1.00	1.00



PRINCIPAL SPILLWAY CONDUIT NOTES

- 30" I.D. BLIND CONC WATER PIPE
 (1) 5' SECTION
 (2) 16' SECTION
 (1) WALL FITTING FOR 10" WALL
 TOTAL = 120.1'
 PRESSURE HEAD = 14'
 LOAD = 10,700 LBS. PER LF. BASED ON 0.01" CRACK
 MIN. 3-EDGE BEARING STRENGTH FOR 0.01" CRACK =
 2,640 LBS. PER LF. FOR PRESTRESSED PIPE ANWA C301
 MIN. 3-EDGE BEARING STRENGTH FOR 0.01" CRACK =
 9,510 LBS. PER LF. FOR NON PRESTRESSED PIPE ANWA C300

Profile Along S of Principal Spillway






①

COLLAR	DIST FROM DRAIN HALL	TOP ELEV OF SP. CO. PIPE
I	21.18	199.12
II	48.33	198.78




JOINT	DIST FROM OUTLET END	INVERT ELEV. SP. CO. PIPE	REMARKS
OUTLET	0	199.24	
1	16.0	199.18	
2	32.0	199.11	
3	48.0	199.03	
4	64.0	198.94	
5	80.0	198.86	
6	96.0	198.78	
7	112.0	198.70	
8	128.0	198.62	

NOTE:
DIMENSIONS AND ELEVATIONS ARE BASED
ON NORMAL TIDE AND DO NOT INCLUDE
SETBACK



2

REPORT TO BUREAU OF REVENUE
OF DISTRICT NO. 1



SPAULDING POND BROOK WATERSHED PROJECT
SPAULDING POND SITE NO 2
NORWICH, CONNECTICUT
PRINCIPAL SPILLWAY

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

Designed by A. L. L. & J. L. 12/65	Approved by 1/66
Drawn by J. L. 12/65	Field 1/66
Traced	By 1/66
Checked	By 1/66
CN - 425 - P	

REFER TO SHEETS 2, 3, 4, 5 FOR LAYOUT OF SPILLWAY



STATE OF CONNECTICUT
WATER RESOURCES COMMISSION
STATE OFFICE BUILDING • HARTFORD 15, CONNECTICUT

January 16, 1967

CONSTRUCTION PERMIT FOR DAM

City of Norwich
Norwich, Connecticut

TOWN: Norwich
RIVER: Shetucket River
TRIBUTARY: unnamed

Attention: Mr. Harold M. Walz, Director
Public Works

Your application for a permit to (~~construct~~) a dam on an unnamed
tributary to Shetucket River, known as Spaulding Pond, Site #2
in the Town of Norwich in accordance
with plans prepared by the Soil Conservation Service
dated December 1965 has been reviewed.

The construction, in accordance with those plans, is APPROVED under the conditions which follow.

- I. The Commission shall be notified as follows:
 - A) When construction is started
 - B) When foundation is excavated
 - C) When dam is complete and before water is impounded
 - D) When project is complete and ready for final inspection.
- II. This permit with the plans and specifications must be kept at the site of the work and made available to the Commission at any time during the construction.
- III. If any changes are contemplated or required, the Commission must be notified and supplementary approval obtained.
- IV. If the construction authorized by this permit is not started within 2 years of the date of this permit and completed within 4 years of the same date, this permit must be renewed.
- V. Additional requirements -

Your attention is directed to Section 25-112 of the 1958 Revision of the General Statutes which states in part regarding this Construction Permit: "A copy of the permit shall be sent to the town clerk." The enclosed carbon copy of this permit is the copy intended for the town clerk and it is your obligation to duly file this copy.

Your attention is further directed to Section 25-115 of the 1958 Revision of the General Statutes - "Liability of Owner or Operator." Nothing in this chapter and no order, approval or advice of the Commission or a member thereof, shall relieve any owner or operator of such a structure from his legal duties, obligations and liabilities resulting from such ownership or operation. No action for damages sustained through the partial or total failure of any structure or its maintenance shall be brought or maintained against the state, a member of the Commission or the Commission, or its employees or agents, by reason of supervision of such structure exercised by the Commission under this chapter."

The Commission cannot convey or waive any property right in any lands of the State, nor is this permit to be construed as giving any property rights in real estate or material or any exclusive privileges, nor does it authorize any injury to private property or the invasion of private rights or any infringement of federal, state or local laws or regulations.

Your attention is also directed to Section 26-134 of the 1958 Revision of the General Statutes - "Obstructing Streams." No person shall, unless authorized by the director, prevent the passing of fish in any stream or through the outlet or inlet of any pond or stream by means of any rack, screen, weir or other obstruction or fail, within ten days after service upon him of a copy of an order issued by the director, to remove such obstruction." The address of the State Board of Fisheries and Game is State Office Building, Hartford, Connecticut.

Very truly yours,

WATER RESOURCES COMMISSION

By: William S. Wise
William S. Wise, Director

WSW:hmy

cc: Fish & Game

UNITED STATES DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE
Lansfield Professional Park
Storrs, Connecticut 06268

August 30, 1968

Mr. Harold M. Walz
Director of Public Works
City of Norwich
Norwich, Connecticut 06360

Dear Mr. Walz:

In accordance with the recommendation made by Mr. Macchi the following information will provide you with a guide as to when it would be advisable to close the Park roads to eliminate possible accidents due to emergency spillway discharges.

The principal spillway (pipe conduit) hydrograph is based on 5 inches of rainfall and associated runoff of about 4 inches or for a rainfall of about 5 inches under normal conditions the emergency spillway may not operate.

The required capacity of the emergency spillway is based on a rainfall of over 16 inches and 15 inches of runoff.

Under this condition the emergency spillway would begin to discharge about 2.5 hours after the start of the design storm. When the pool is 0.6 feet below the crest of the emergency spillway or 1.2 feet below the top of the inlet riser, there would be 27-acre-feet of temporary storage which could result from 2.5 inches of runoff or about 3.5 inches of rainfall.

Time and intensity are factors which are not apparent in the two conditions above.

It is suggested that the Park roads be closed when there is continuing intensive rainfall following rainfall of 3 to 4 inches within two hours, or when the flood pool is 1.2 feet below the top of the inlet riser (Slide 2) and still rising.

Sincerely yours,



T. R. Wire
State Conservation Engineer

cc:
Mr. A. J. Macchi ✓

STATE WATER RESOURCES
COMMISSION
RECEIVED

SEP 10 1968

ANSWERED _____
REFERRED _____
FILED _____



STATE OF CONNECTICUT

WATER RESOURCES COMMISSION

STATE OFFICE BUILDING • HARTFORD 15, CONNECTICUT

September 17, 1968

CERTIFICATE OF APPROVAL

City of Norwich
Norwich,
Connecticut

TOWN: Norwich
RIVER: Shetucket River
TRIBUTARY: Unnamed
CODE NO.: T 14.7 SO.2 U1.3

Attention: Mr. Harold M. Walz, Dir.
Public Works

Dear Mr. Walz:

NAME AND LOCATION OF STRUCTURE: Spaulding Pond Dam Site #2 approximately
200 feet north of Mohegan Park Road and approximately 800 feet west of
Curtis Street in the Town of Norwich

DESCRIPTION OF STRUCTURE AND WORK PERFORMED: Construction of an earth
dam approximately 180 feet in length and 9 feet in height and an earth
dike approximately 1120 feet in length and 19 feet in height in accordance
with plans prepared by the U. S. Department of Agriculture, Soil Con-
servation Service dated:

CONSTRUCTION PERMIT ISSUED UNDER DATE OF: January 16, 1967

This certifies that the work and construction included in
the plans submitted, for the structure described above, has been
completed to the satisfaction of this Commission and that this
structure is hereby approved in accordance with Section 25-114
of the 1958 Revision of the General Statutes.

The owner is required by law to record this Certificate in
the land records of the town or towns in which the structure is
located.

WATER RESOURCES COMMISSION

BY: J. J. Curry, Director

This floodwater retarding dam is located on Spaulding Pond Brook, immediately outside the northerly limit of the City of Norwich. Sheet 4 of this report, together with the Norwich 7.5 minute quadrangle published by the U.S. Geological Survey, may be used to locate the structure more accurately.

A summary of pertinent design information is given on sheet 2 of this report.

Criteria and procedures used in this design are given in the following Soil Conservation Service publications:

- National Engineering Memorandum No. 27, Limiting Criteria for the Design of Earth Dams
- National Engineering Memorandum No. 42, Reinforced Concrete Pipe Drop Inlet Barrels
- National Engineering Memorandum No. 50, Drop Inlet Spillway Standards
- National Engineering Handbook No. 4A, Hydrology
- National Engineering Handbook No. 5, Hydraulics
- National Engineering Handbook No. 8, Geology
- Engineering Division Technical Release No. 2, Earth Spillways
- Engineering Division Technical Release No. 5, Structural Design of Underground Conduits
- Engineering Division Technical Release No. 10, Storage-Floodwater Retarding Structures
- Engineering Division Technical Release No. 12, Procedure for Computing Sediment Requirements for Retarding Reservoirs
- Weather Bureau Technical Paper No. 40
- Weather Bureau Technical Paper No. 29

This structure is one of two flood retention structures designed to reduce flood damages in the flood plain of this watershed. It will retard the runoff from a 100-year frequency storm without discharge occurring in the emergency spillway.

The results of hydrologic and hydraulic computations are given on sheet 3 of this report.

This structure consists of a compacted earth fill with a cutoff extending into the foundation. A drainage system is located under the downstream portion of the fill to collect and safely discharge any seepage that may develop through the embankment and foundation with the impoundment of floodwaters.

The principal spillway is a drop inlet structure consisting of a two-stage reinforced concrete riser, 30-inch diameter conduit of reinforced concrete water pipe, and a riprap outlet basin to dissipate energy at the outlet end of the conduit.

The emergency spillway is designed as an earth cut in the left abutment.

U S DEPARTMENT OF AGRICULTURE - SOIL CONSERVATION SERVICE

DESIGN REPORT SUMMARY

I. Watershed data

A. Structure class	<u>c</u>	
B. Drainage area	<u>132</u>	Ac.
C. Time of concentration - T _c	<u>0.5</u>	Hrs.
D. Hydrologic curve number - C _n		
1. Moisture condition II	<u>75</u>	
2. Moisture condition III	<u>91</u>	

II. Principal spillway


A. Conduit		
1. Size (I.D.)	<u>30</u>	In.
2. Length	<u>118.1</u>	Ft.
B. Riser		
1. Size	<u>2.5 x 7.5</u>	Ft.
2. Height	<u>10.3</u>	Ft.
C. Weir length	<u>15</u>	Ft.
D. Orifice size	<u>12 x 20</u>	In.
E. Pond drain size	<u>12</u>	In.
F. Type of energy dissipator	<u>riprap basin</u>	

III. Emergency spillway

A. Width	<u>100</u>	Ft.
B. Side slopes	<u>3:1</u>	
C. Length of level section	<u>100</u>	Ft.
D. Exit slope	<u>0.021</u>	Ft./Ft.
E. Maximum velocity at control section (D.H.W.)	<u>6.9</u>	Ft./Sec.
F. Duration of flow (D.H.W.) through emergency spillway	<u>8.8</u>	Hrs.
G. Frequency of use	<u>once in 100-years</u>	

IV. Earth fill

A. Height	<u>16</u>	Ft.
B. Volume	<u>18,500</u>	C.Y.
C. Compaction	<u>Class A</u>	



Typical Cross Section

U S DEPARTMENT OF AGRICULTURE - SOIL CONSERVATION SERVICE

Element of Structure	Determining Factor	Elevation	Surface Area Acres	Storage		Inflow		Peak Outflow c.f.s.
				Acre-Feet	Inches*	Volume Inches*	Peak Rate c.f.s.	
Invert of orifice	50-year sediment accumulation	159.0	1.8	0.9	-	-	-	20.9
Crest of riser	100-year frequency ^{1/} storm, 6 hr. duration moisture condition II	166.3	4.6	24.0	2.18	2.52	205	84
Crest of emergency spillway	100-year frequency ^{2/} storm, 6 hr. duration, moisture condition III	167.6	5.4	30.2	2.74	4.08	367	75
Design high water	16.5 in. rainfall, ^{2/} moisture condition III	170.3	7.1	47.6	4.33	15.38	1312	1094
Top of dam ^{3/}	Design high water ^{2/} elevation plus 2 ft.	172.3	8.8	54.2 ^{4/}	4.93 ^{4/}	21.89 ^{4/}	1928 ^{4/}	1760 ^{4/}

* Volume expressed in inches of runoff from controlled watershed area of 132 acres.

^{1/} Work Plan evaluation storm

^{2/} State of Connecticut, Water Resources Commission, criteria

^{3/} Maximum elevation as determined by (a) routing 1.0 x value from ES-1020 sh. 5, moisture condition III (SCS freeboard hydrograph, National Engineering Memorandum SCS-27)

(b) Design high water elevation plus 2 feet

^{4/} Value obtained from SCS freeboard hydrograph routing

Time required to empty flood storage is 1.45 days.

ENGINEERING & WATERSHED PLANNING UNIT, UPPER DARBY, PA

STATE Connecticut

PROJECT Spaulding Pond Brook, Site #2

BY WHL DATE

CHECKED BY DATE

JOB NO

CN 425-H

SUBJECT

NARRATIVE

SHEET

OF

A. General

In view of the scarcity of borrow material at Site No. 1 where, as a final resort, borrow was taken from the pool, it was decided to utilize the available borrow in the pool at Site No. 2 and account for the resulting flood storage in the routings. This additional storage allowed the top of dam to be lowered 3.5' below the work plan estimate, resulting in a considerable decrease of compacted fill. The borrow removal also saved the cost of excavating a ditch from the woods road to the riser to allow drainage of the pool area east of the woods road. The increased storage permitted the emergency spillway to be lowered approximately 4' below the work plan estimate which then allowed the spillway to be moved from the right abutment to the left abutment. Not only did this save the cost of excavating approximately 600 c.y. of rock, but appears to present a much more useable source of borrow material. The flood storage obtained by the removal of borrow will be verified after excavation.

The Principal Spillway elevations were established by three main factors:

1. an elevation low enough to allow the use of as much storage east of the woods road as feasible.
2. the presence of rock near the outlet end of the pipe and in the outlet channel.
3. an elevation at the inlet end to which the pool borrow area (Borrow Area "A") could be drained during excavation.

The orifice was located at elevation 159.0 with the proposed limit of borrow excavation at elevation 158.5 to insure the provision of sufficient sediment storage.

The flood routing were based upon the runoff from the entire watershed (0.207 sq.mi.) initially neglecting the fact that the pool area was divided by a saddle. To the inflow hydrographs were added the respective outflows from Site No. 1, with the exception of the high stage hydrograph. Here, lacking a high stage routing for Site No. 1, the principal spillway outflow hydrograph (AMCIII) was added to the high stage inflow hydrograph (AMCII) yielding slightly conservative results. The outflow from Site No. 1 was lagged 1/2 hour to account for the travel time plus retardance due to both localized pockets of valley storage and a restriction created by a small road culvert.

During the initial stages of design, consideration was given to a second principal spillway through the dike east of the woods road which would serve to drain the small pool area. This would have been required to discharge approximately 12.8 AF through the dike and out of the watershed. As an alternative to this, it was decided to place a connecting culvert under the woods road (under the gas transmission line). The capacity of the culvert was then checked using both the

STATE	Connecticut	PROJECT	Spaulding Pond Brook, Site #2		
BY	WHL	DATE	CHECKED BY	DATE	JOB NO
					CN 425-II
SUBJECT	NARRATIVE				SHEET 1 OF 1

principal spillway storm and the emergency spillway design storm to insure that it did not retard flow from the main pool to the small pool. During the principal spillway storm, flow through the culvert was mainly out of the main pool, but at $T=3.9$ hrs. (w.s. elevation slightly below the emergency spillway crest) the flow reversed, thus precluding the possible existence of a higher stage in the main pool.

During the emergency spillway design storm flow through the culvert is again mainly directed out of the main pool. At $T=2.1$ hr. the water surfaces equalize only to have the water surface elevation in the main pool again rise above that east of the woods road. At $T=2.4$ hr. flow across the woods road occurs (from west to east) equalizing the water surfaces before the Design High Water Elevation is attained, thus not affecting the routine.

B. Connecting Culvert Flow Computations

These computations consist of determining, for each of the two pool areas, the amount of inflow during a given time interval and the resulting water surface elevations. The amount of inflow was determined from the area between the inflow and outflow hydrographs for the given time interval. The resulting water surface elevations were then used to determine the amount of flow through the connecting culvert during the time interval from the head-discharge curve. The Q_{av} curve was determined by assuming that the flow varied from a maximum value at the beginning of the time interval to zero at the end of the interval (water surf. elevs. equal @ end of interval). This was found not to be the case, but rather that the flow was greater than zero at the end of the interval, thus resulting with a larger value of average flow. This was corrected by determining, at the end of each time interval, the increase in Q from the resulting water surface elevations at the end of that interval.

The water surface profiles through the culvert were used to obtain the amount of flow and the resulting gradient between the water surface elevations at each end of the culvert before full-pipe flow occurred.

COMPUTATION SHEET
SCS-523 REV 5-58


U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

LPO 1958 O 67586

STATE Ill. PROJECT Spaulding Pond Basin, Site #2
BY WML DATE 10/25/65 CHECKED BY WTF DATE 12-7-65 JOB NO. CH-475-H
SUBJECT Stage Storage - W. Side of Wood Road SHEET 5 OF 50

Including storage due to borrow removal

Elev.	Area Ac.	Avg. Area Ac.	Contour Int. Ft	Volume Ac-Ft	Accum Stor. Ac Ft	Avail Stor. Ac Ft
159	1.8		2'	3.75	0	0
160	1.95			4.16	3.75	3.75
162	2.21			4.57	7.91	7.91
164	2.46			5.20	12.50	12.50
166	2.74			6.24	17.75	17.75
168	3.50			7.79	24.52	24.52
170	4.39			9.75	31.81	31.81
172	5.46			12.66	41.56	41.56
174	7.20			16.21	54.22	54.22
176	9.01				70.43	70.43



STATE	Conn.	PROJECT	Spaulding Pond Lower Site 2		
BY	WTF	DATE	11/64	CHECKED BY	WHL
		DATE	2/3/65	JOB NO.	CN-425-11
SUBJECT	Stage - Storage Data				SHEET 6 OF 50

Stage-Storage Data East of Wood Road

Elev.	Area - Ac.	Av. Area - Ac.	Contour Int.	Vol. - Ac-Ft	Area - Sq. Ft.	Area - Sq. Ft.
157.5	0	0.06	0.5'	0.03		0
158	0.11	0.27	2'	0.34	3.03 AF	0
160	0.42	0.60	2'	1.20	3.57	0
162	0.77	1.00	2'	2.00	1.71	0
164	1.24	1.46	2'	2.92	3.77	2.30 AF
166	1.67	1.88	2'	3.76	6.69	4.92
168	2.08	2.34	2'	4.68	10.45	8.68
170	2.60	2.78	2'	5.56	15.13	13.56
172	2.96	3.22	2'	6.14	20.69	18.32
174	3.48	3.77	2'	7.54	27.13	25.32
176	4.06		2'		34.67	32.90

Storage below elev. 162 unavailable for flood storage.

COMPUTATION SHEET
SCS-523 REV 5-58

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

STATE Conn. PROJECT Found. for 1st 1/2 mi. of road
BY WHL DATE 10/25/65 CHECKED BY D.S. DATE 12/7/65 JOB NO. 100-1-1
SUBJECT Combined Stage Storage Data SHEET 7 OF 21

Pool area east of wood rd. filled with spoil to elev 162

Elev	Avail. Stor E. of rd	Avail Stor W of rd	Avail Stor Total
159	0	0 AF	0 AF
160	0	3.75	3.75
162	0	7.91	7.91
164	2.0 AF	12.58	14.58
166	4.92	17.78	22.70
168	8.68	24.02	32.70
170	13.36	31.81	45.17
172	18.92	41.56	60.48
174	25.36	54.22	79.58
176	32.90	70.43	103.33

STATE	Conn.	PROJECT	Spaulding Pond Brook, Site 2		
BY	WHL	DATE	2/4/65	CHECKED BY	WTF
		DATE	2/6/65	JOB NO.	CN-425-H
SUBJECT	Principal Spillway Discharge Data				SHEET 8 OF 50

Two-Stage Riser - Floor Elev. 156.0

Outlet Invert Elev. = 155.0

Elev of C of Outlet = 156.25

Low Stage - Orifice 1'-8" wide by 1'-0" high @ elev. 159.0

Assume discharge coeff. = 0.6

$$Q = CA\sqrt{2gh} = 0.6 (1.67') (8.02') \sqrt{H} = 8.02 \sqrt{H}$$

High Stage - Weir (30" I.D. conduit)

weir length = (2.5' (3)) \approx 15'

$$Q_w = CLH^{3/2} \quad \text{where } C \approx 3.1$$

$$\therefore Q_w = 3.1 (15) (H^{3/2}) = 46.5 H^{3/2}$$

Pipe Flow

$$n = 0.012 \text{ (Manning) } \quad A_p = 4.91' \quad L_p = 140' \quad K_p = 0.00786$$

$$K_p L_p = 140 (0.00786) = 1.10$$

$$K = \left(\frac{1}{K_e + K_c + K_p L_p} \right)^{1/2} = \left(\frac{1}{3.10} \right)^{1/2} = \sqrt{0.323} = 0.568$$

K_e = entrance loss = 1.0

K_c = exit loss = 1.0

$$Q_p = KA_p \sqrt{2gH} = 0.568 (4.91) (8.02') H^{1/2} = 22.4 H^{1/2}$$

COMPUTATION SHEET
SCS-523 REV 5-58

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

GPO 1958 O-670887

STATE <u>Conn</u>		PROJECT <u>Spaulding Pond Brook, Site 2</u>		
BY <u>WHL</u>	DATE <u>10/22/65</u>	CHECKED BY <u>D.S.</u>	DATE <u>12/7/65</u>	JOB NO. <u>3N-425-H</u>
SUBJECT <u>Stage-Discharge Data</u>				SHEET <u>9</u> OF <u>50</u>

outlet inv. elev. 158.0

± outlet elev. 156.25

orifice crest elev. 159.0

± orifice elev. 159.5

Elev.	Orifice Flow (159.5)		Weir Flow (166.8)			Pipe Flow (156.25)		Resultant Flow cfs
	h_o	$Q_o = 8.02 \sqrt{h_o}$	h_w	$h_w^{3/2}$	$Q_w = 46.5 H_w^{3/2}$	h_p	$Q_p = 27.4 h_p^{1.48}$	
159	0	0						0
160	0.5	5.7						5.7
161	1.5	9.8						9.8
162	2.5	12.7						12.7
163	3.5	15.0						15.0
164	4.5	17.0						17.0
165	5.5	18.8						18.8
166	6.5	20.4						20.4
166.3	6.8	20.9	0	0	0			20.9
166.6	7.1	21.3	0.3	0.164	7.6			28.9
166.9	7.4	21.8	0.6	0.465	21.6			43.1
167.2	7.7	22.2	0.9	0.854	39.7	10.95	74.1	61.9
167.5	8.0	22.7	1.2	1.315	61.1	11.25	75.1	75.1
167.6						11.35	75.1	75.1
168						11.75	76.7	76.7
170.3						14.05	84	

STATE	Conn.	PROJECT	Spaulding Pond Brook Site 2	
BY	WVL	CHECKED BY	NTF	DATE
SUBJECT	Emergency Spillway Hydraulics			JOB NO. CN-465-M
				SHEET 20 OF 50

inlet length = 160' $S_0 = 0\%$ $b = 100'$ $Z = 3'$

control sect elev. = 167.6'

q	d_c	$Z d_c$	$b + Z d_c$	$Q = 3(b + Z d_c)$	H_p	W.S. Elev.
2	0.5	1.5	101.5	203.0	1.1	168.70
5	0.92	2.76	102.76	314	1.88	169.48
7	1.15	3.45	103.45	724	2.28	169.88
10	1.46	4.38	104.38	1044	2.76	170.36
12	1.65	4.95	104.95	1259	3.10	170.70
15	1.91	5.73	105.73	1586	3.49	171.09
17	2.09	6.27	106.27	1807	3.8	171.40
20	2.33	6.99	106.99	2140	4.11	171.71

W.S. Elev.	H_{pipe}	$H_{fr}^{1/2}$	$Q_p = 22.4 H_p^{3/2}$	Q_{em}	Total Q
168.70	12.45	3.53	79.1	203	282
169.48	13.23	3.64	81.5	314	396
169.88	13.63	3.69	82.6	724	807
170.36	14.11	3.75	84.0	1044	1128
170.70	14.45	3.80	85.1	1259	1344
171.09	14.84	3.85	86.2	1586	1672
171.40	15.15	3.88	86.9	1807	1894
171.71	15.46	3.93	88.4	2140	2228

STATE Ore. PROJECT Building Flood Control Dam
BY UWML DATE 10/2/56 CHECKED BY DS DATE 10/11/56 JOB NO. 100-1-11
SUBJECT Emergency Spillway Hydraulic Control SHEET 11 OF 20

from emer. spw. design hydrograph:

design high water - elev. 170.3'

total discharge - 1074 cfs

@ elev. 170.3', $Q_p = (170.3 - 156.65) (2.4) = 34$ cfs

$Q_{em} = 1074 - 34 = 1040$ cfs

$Q_{em}/b = 10.4 \frac{\text{cfs}}{\text{ft}}$

$S_o = 2.1\%$ $V = 7.55 \text{ fps}$

$H_p = 2.8'$ (from plot of H_p vs Q_{em})

$d_c = 1.47'$ (eq. 4b) $V_c = 6.9 \text{ fps}$

$A = \frac{Q}{V} = \frac{1040}{7.55} = 137.8' = (b + 3d) d$ where b is in feet

$(100 + 3d)(d) = 137.8$

$3d^2 + 100d - 137.8 = 0$

$d^2 + 33.3d - 44.6 = 0$

$d = \frac{-33.3 \pm \sqrt{(33.3)^2 + 4(44.6)}}{2}$
 $= \frac{-33.3 \pm 41.4}{2}$
 $= \frac{8.1}{2} = 4.05'$

Soil type: Hollis (shallow silty soil)

refer - TSC ENG. MEMO UD-3

Allowable velocity =

for seed mixtures #2 thru 7, 0-5% grade

erosion resistant soil - $V = 7 \text{ fps}$

easily erodible " - $V = 5 "$

use $V = 6 \text{ fps}$

for once in 100 yrs.

$V_{\text{allow}} = 6(1.25) = 7.5 \text{ fps}$ say OK

GEOLOGY REPORT

CN - 60
JAN. 1959

STORAGE ALLOCATION

	<u>Depth at Dam</u> (feet)	<u>Surface Area</u> (acres)	<u>Volume</u> (ac. ft.)
Sediment:	1.4	1.0	0.4
Floodwater:	14.0	8.3	45.0

B. Surface Geology and Physiography

Site No. 2 at Spaulding Pond Brook is located in the Eastern Metamorphic Highlands of Connecticut. The area of the site is of gentle topographic expression set in a region of moderate to steep relief. The structure consists of a main dam approximately 285 feet long and an adjoining dike approximately 1200 feet long. The centerline of the dam crosses a pond impounded by a small concrete and granular fill dam. The right and left abutments (looking downstream) have slopes of approximately 9 percent each.

The bedrock as exposed and/or encountered in drilling is the Putnam Gneiss of probable Precambrian age. This formation is composed of four different mappable phases; the predominant one in the watershed being the Sillimanite-pinite schist. Rocks of this phase are gray to brown and medium to coarse-grained. Principal mineral constituents are quartz, biotite, feldspars, and iron minerals. Surficial deposits are of glacial origin consisting almost primarily of a thin layer of till which generally reflects the bedrock topography and is referred to as ground moraine. Within the till highly varied soil types may be found ranging from stream-deposited sands and gravels to compact clayey tills.

No structural features were observed at the site. Strike of the bedrock is not consistent in the watershed because of the distortion of the rock; however the dip as observed in most cases is very steep but again varying considerably in direction. Present channel conditions are stable and no erosion problem is anticipated since the outlet of the channel is on bedrock.

REFERENCE:

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

DRAWING NO.

CN 425-G

SHEET 2 OF

DATE 1/6/59

GEOLOGY REPORT

CN - 60
JAN. 1959

II. Subsurface Geology

A. Centerline of Dam

Thirteen holes were drilled either on or near the centerlines of the proposed dam and dike. All holes were sampled with a split-spoon sampler using standard penetration resistance and all bedrock was diamond cored to a minimum penetration of 5.0 feet. All holes drilled encountered bedrock with the exception of #54 which went to a depth of 21.0 feet where the blow count on the sampling spoon was in excess of 250 blows per foot.

The material encountered in all holes with the exception of those in or on the periphery of the existing pond (holes 53 and 54) is essentially the same; that being very fine to fine grained poorly graded sand with varying amounts of non-plastic fines. Generally the blow count indicates that the sand has a dense to very dense relative density beyond a depth of 5.0 feet. Characteristic with the morainal type cover, very little stratification is present in those areas drilled and that which may occur is very local and not extensive. In hole 53 which was drilled in the existing pond from a barge, about 2.5 feet of highly plastic silt was penetrated immediately underlain by a very dense, very fine grained sand. Fragmental rock up to 1" size was present throughout the section and was estimated 5 to 10 percent by volume. In hole 54, a very fine grained sand with associated low plasticity fines was drilled. This zone (visually identified) was encountered at 8.0 feet and extended to 13.5 feet.

The bedrock profile on the basis of exposure and drill hole information is highly irregular and does not assume any reliable lateral continuity. The bedrock varies considerably in texture, type and mineral constituents. The bedrock which is primarily the schist phase of the Putnam Gneiss formation, ranges from a very fine grained biotitic, feldspathic schist to a highly quartzitic schist where the rock texture is almost massive. Bedding planes in the core range from horizontal to almost vertical again attesting to the lack of uniformity in the attitude of the bedrock throughout the site. Fracturing is common in most of the bedrock drilled

REFERENCE:

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

DRAWING NO.

CN 425-G

SHEET 3 OF

DATE 7/65

GEOLOGY REPORT

JAN. 1959

with the greatest percentage of fracturing being horizontal. Oxidation was noted along fracture faces in holes 51 and 52. The bedrock cored in the remaining holes was in generally good condition and unweathered.

Groundwater levels are within 5 to 7 feet of ground surface elevations in most of the holes drilled. No groundwater levels could be detected in holes 56 and 57. No groundwater measurement was made in hole No. 55.

Surface boulders were common throughout the site and the presence of boulders in several of the holes necessitated drilling with a diamond bit.

B. Centerline of Outlet Structure

Five holes were drilled along an axis paralleling the centerline of the proposed conduit. Holes 310 and 311 were drilled in the existing pond from a barge. Hole 312 was located on and drilled through the existing structure. Holes 313 and 314 were located on natural ground surface. It should be noted that all hole depths in nos. 310 and 311 have been measured from the raft deck which is 2.0 feet above pond level. In hole 310, 3.5 feet of low-volume weight material was visually classified as a low plasticity organic silt (OL). This was underlain by fine to medium grained silty sand which attained a very dense relative density by 15.5 feet or 11.5 feet from pond bottom. Bedrock was encountered at 35.0 feet.

In hole 311, almost 3.0 feet of low plasticity organic silt extended from existing pond ^{bottom} to about a depth of 7.0 feet from the raft deck. From 9.0 to 13.5 feet a layer of fine to medium grained, poorly graded, well oxidized sand was entered. The fines were non-plastic and estimated from 5 to 12 percent. A very dense relative density was not attained until about 25.5 feet. Bedrock was not encountered until 29.5 feet at which depth 5.0 feet of silt was cored.

Hole 312 was located on and drilled through 5.0 feet of granular sand and gravel fill of the existing embankment. This was underlain by a very dense silty sand which graded

REFERENCE:

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

DRAWING NO.

CN 425-G

SHEET 4 OF

DATE

7/65

GEOLOGY REPORT

CN - 60
JAN. 1959

into a very dense and very fine grained sand at 13.5 feet. This material continued to the point of refusal on the sampling spoon at 31.0 feet where rock core drilling commenced. At a depth of 14.0 feet the driller made a notation on his log of an artesian condition, however no measurement of head was made. Since this condition was not observed in the field at the time it is uncertain whether or not the notation on the log represented a true artesian flow.

In hole 313, no split spoon samples could be obtained for the first 7 feet because of a dense boulder concentration. Because of its proximity to adjoining holes, the material is probably the same, that being a fine grained silty sand visually classified as SM. Bedrock was hit at 7.0 feet and was diamond cored for 5.0 feet making a total hole depth of 12.0 feet. The bedrock was in good condition being generally unweathered.

Hole 314 penetrated a dark brown organic silty sand for the first 2.0 feet and has tentatively been classified as OL. From 2.0 to 9.0 feet the material was a very fine to fine grained silty sand with decomposed schist fragments from about 4.0 feet. Refusal was met at 9.0 feet and diamond drilling was performed from 9.0 to 12.0 feet. The bedrock (schist phase of the Putnam Gneiss) was fine grained, with near vertical bedding planes. The rock was well fractured to 11.0 feet with oxidation following the bedding planes of the schist. Generally the rock was well fractured throughout most of the section cored.

C. Emergency Spillway

Eight holes were drilled in the proposed emergency spillway area to evaluate subsurface materials and to delineate the underlying bedrock. All holes drilled penetrated bedrock. The most conspicuous factor was the irregularity of the bedrock surface. Depth to bedrock ranged from 1.0 foot in hole #218 where surfaces outcropping was common to 22.0 feet and 25.0 feet in holes 214 and 216 respectively. The bedrock drilled in holes 214 and 216 was composed of soft decomposed biotitic schist. Core recovery from both these holes was poor with the best recovery being obtained in hole 216 in the last 5 feet run from 38 to 43 feet. Core recovery in this interval was 78 percent.

REFERENCE:

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

DRAWING NO.

CN 425-G

SHEET 5 OF

DATE 7/65

G E O L O G Y R E P O R T

CN - 60
JAN. 1959

The materials comprising the substratum are primarily a very fine to fine grained sand being poorly graded with non-plastic fines estimated from 15 to 20%. Fragmental rock is estimated at 20-30%. A general thickening towards the north or towards the entrance channel is apparent in the substratum and conversely the depth to bedrock becomes shallow approaching the exit channel toward holes 213 and 215.

Bedrock excavation should be anticipated in portions of the emergency spillway to meet design grades. The probable area of anticipated rock excavation is indicated by the following drill holes where bedrock was encountered above design grade: Nos. 211, 217 and 218. The emergency spillway when completed at grade will be on both bedrock and fairly well consolidated silty sands with fragmental rock, cobbles, and boulders. The outer portions of the exit channel should present no problem with regard to stability since most of it should be on bedrock.

D. Borrow Areas

The primary source of borrow (designated Borrow "A") is approximately 700 feet north of the proposed dam. It has the configuration of a conical-shaped hill with three gently sloping sides of approximately 9% with the steepest side towards the west or pool side having a slope of about 20%. One backhoe pit (#178) was dug on the crest of the hill to a depth of 8.1 feet. The material encountered as visually identified is a very fine to fine grained sand with non-plastic fines estimated about 12 to 15%. The material has been tentatively classified as an SM in the Unified Soil Classification System. A sample of the material from #178 was sent to the Soil Mechanics Laboratory for analysis to determine the suitability of the material for fill. In addition to pit #178, pits 179, 180, 190 and 191 were dug on the southern fringe of the proposed main borrow area. Pit 179 went to a depth of 9.1 feet. The material has been tentatively classified as SP-SM. Pit 180 was dug on the east flank of the borrow area near a natural gas line. Bedrock outcropping is common throughout this area and pit 180 was probably bottomed on bedrock at 2.7 feet. Pits 180 and 191 were dug on the southern periphery of the borrow area. The pits are approximately within the normal pool level and the material tentatively identified as SM.

REFERENCE:

U. S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

DRAWING NO.
CN 425-G

SHEET 6 OF

DATE 7/65

G E O L O G Y R E P O R T

In pit 191 water was encountered at three (3) feet and was present throughout the whole section of hole beyond 3.0 feet.

Within the existing pond, holes 601, 602 and 603 were drilled from a barge to evaluate materials as a possible borrow alternate. A maximum depth of 37.3 feet was attained in hole 601 before refusal was obtained on the split spoon sampler. The material in the three holes were essentially the same being fine grained silty (non-plastic) sand. Apart from being well saturated a mantle of low plastic organic silts are present from existing pond bottom to about 8 feet as seen in hole 601. This area has been referenced Borrow Area "B".

Borrow Area "C" in the emergency spillway area represents that material which may be salvaged during common excavation in setting the design spillway grade.

REFERENCE:

U.S. DEPARTMENT OF AGRICULTURE
SOIL CONSERVATION SERVICE

DRAWING NO.
CN 425-G

SHEET 7 OF

DATE 7/65

rev. 9-21-66

SFD 10580-470007

STATE	Conn.	PROJECT	Spaulding Pond Brook, Site 2		
BY	WHL	DATE	CHECKED BY	DATE	JOB NO.
		2/8/66			CN-425-Q
SUBJECT	Quantity Summary				SHEET 1 OF 43

Compacted Fill, Class A

Dam embankment	+ 2,300 c.y.
" cutoff trench	+ 640
Principal Spillway backfill (= excav. - drain fill)	+ 510
	- 48 (drain fill)
Dam - Drain Fill above fdn. line	- 9
Dike embankment	+ 15,048
" cutoff trench	814
Dike - Drain Fill above fdn. line	- 88
Connecting Culvert backfill (= excav.)	+ 193
Net =	19,345 c.y.

Drain Fill

Dam - drain	170 c.y.
Dike - drain	241
Outlet Basin & Channel	36
Under riprap - face of dam	44
Total =	491 c.y.

Riprap - Hand placed

Outlet Basin & Channel	152 c.y.
Connecting Culvert	31
Face of dam	169
End of Outlets	5
Total =	357 c.y.

STATE	Conn.	PROJECT	Spaulding Pond Brook Site 2
BY	WHL	DATE	2/8/66
CHECKED BY		DATE	
SUBJECT	Quantity Summary - cont'd		JOB NO. CN-425-2
			SHEET 2 OF 42

Excavation Common

Dam Foundation	996	cu.
" Cutoff	640	
Principal Spillway	546	
Dam Seepage Drain	61	
Outlet Basin & Channel	950	
Dike Foundation	2972	
" Cutoff	814	
" Seepage Drain	132	
Connecting Culvert Litch	887	
Excav	193	
Total	8,185	cu.

Excavation Rock

Prim. Sping. & Outlet channel	34	cu.
Dam Boulder estimate	30	
Dike	60	
Diversion	20	
	144	
SAY	150	cu.

STATE <u>Conn</u>		PROJECT <u>Spring Pond Road Site</u>		
BY <u>WRL</u>	DATE	CHECKED BY	DATE	JOB NO. <u>IN-4</u>
SUBJECT <u>Quantity Summary - cont'd</u>				SHEET <u>3</u> OF <u>43</u>

Clearing and Grubbing

Ditch and Spurg. No. 2

Dike area

Division (incl. barbed wire)

Clearing, Class A

Ditch 1 Area No. 1

" " No. 2

APPENDIX C

PHOTOGRAPHS